STATE OF VERMONT
AGENCY OF TRANSPORTATION

# CHANGE ORDER TRAFFIC SIGN SUMMARY SHEET 1 A

RSG INC.

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | SALVAGE | NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) lb/ft 1.75 1.88 | 2.0 2.16 | 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | 4.0 1.7 | 4.0 MOD 1.7 | FOUND-ATION | TUBULAR STEEL Ø (in) lb/ft 3.0 7.6 | 3.5 9.0 | 4.0 10.8 | 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGNS REQUIRED | REMARKS | SIGN DETAIL DETAIL ON SHEET NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | |
| 52+57 ℄ | | 1 | 36 | 36 | 9 | | | | | | | | | | | | | | | | | | | | | | | | | | | | MUTCD R3-18 INSTALL IN PLACE OF REMOVED R3-4 | | |
| 56 ~~55+12~~ 56+83 RT | | 1 | 36 | 36 | 9 | | | | | | | | | | | ~~12.5~~ 14.25 | | | | | | | | | | | | | | | | | MUTCD W4-1 | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 58+30 LT | | 1 | 36 | 30 | 7.5 | | | | | | | | | | | 13.5 | | | | | | | | | | | | | | | | | VR-924 | | E-145A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 60+87 LT | SHARE THE ROAD | 1<br>1 | 30<br>18 | 30<br>24 | ~~6.3~~ 6.25<br>3 | | | | | | | | | | | | ~~15.5~~ 15.25 | | | | | | | | | | | | | | | | MUTCD W11-1, W16-1P | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 61+00 RT | BIKE LANE AHEAD | 1<br>1 | 24<br>24 | 18<br>8 | 3<br>1.33 | | | | | | | | | | ~~13.2~~ 12.75 | | | | | | | | | | | | | | | | | | MUTCD R3-17, R3-17aP | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 61+41 RT | ONLY | 1 | 36 | 30 | 7.5 | | | | | | | | | | | 13.5 | | | | | | | | | | | | | | | | | VR-922 (MOD.) | | E-145A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 62+73 LT | ONLY BIKE LANE ENDS | 1<br>1<br>1 | 36<br>24<br>24 | 30<br>18<br>8 | 7.5<br>3<br>1.33 | | | | | | | | | | | | 14.7 ~~14.75~~ | | | | | | | | | | | | | | | | VR-922 (MOD.)<br>MUTCD R3-17, R3-17bP | | E-145A |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 63+33 LT | END CENTER LANE ONLY | 1<br>1 | 30<br>24 | 12<br>36 | 2.5<br>6 | | | | | | | | | | | ~~15~~ 14.75 | | | | | | | | | | | | | | | | | MUTCD R3-9dP, R3-9b | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 63+33 RT | BEGIN CENTER LANE ONLY BIKE LANE | 1<br>1<br>1 | 30<br>24<br>24 | 12<br>36<br>18 | 2.5<br>6<br>3 | | | | | | | | | | | | 15.5 ~~15.25~~ | | | | | | | | | | | | | | | | MUTCD R3-9dP, R3-9b, R3-17 | | |
| | | | | | | | | | | | | FT | FT | FT | FT | FT | FT | | EA | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| | | | | | | | | | | | | | | | ~~13.2~~ 12.75 | ~~54.5~~ 56 | ~~45.7~~ 45.25 | | | | | | | | | | | | | | | | | | |
| **TOTALS** | | | | | ~~78.4~~ 78.41 | SF | EA. | SF | | | | FT | | | FT | | ~~113.4~~ 114.0 | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BURLINGTON-SOUTH BURLINGTON
PROJECT NUMBER: NH 2624(I)

FILE NAME: p06d216.dgn
PROJECT LEADER: MJS
DESIGNED BY: CDM
IPARM FILE: p06d216l35.i
PLOT DATE: 05/07/12
DRAWN BY: CDM
CHECKED BY: MJS
SHEET 12 OF 14

✓ J.M 8/14/13