

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	LANDSCAPING	EROSION CONTROL	FULL E.C. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							116				116		CY	COMMON EXCAVATION	203.15				
							17				17		CY	SAND BORROW	203.31				
							520				520		CY	TRENCH EXCAVATION OF EARTH	204.20				
							50				50		CY	TRENCH EXCAVATION OF ROCK	204.21				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
							200				200		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							55				55		LF	24" CSP .064 (2-2/3 X 1/2)	601.0025				
							68				68		LF	24" CPEP	601.0920				
							1				1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18				
							1				1		EACH	PRECAST REINFORCED CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.20				
							142				142		LF	12 INCH UNDERDRAIN PIPE	605.13				
							40				40		HR	BULLDOZER RENTAL, TYPE I	608.10				
							40				40		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							10				10		HR	POWER BROOM RENTAL, TYPE I	608.30				
							20				20		HR	TRUCK RENTAL	608.37				
							40				40		HR	LOADER RENTAL, TYPE I	608.40				
							265				265		CY	STONE FILL, TYPE II	613.11				
							3575				3575		CY	STONE FILL, TYPE III	613.12				
							40				40		LF	REMOVE AND RESET GUARDRAIL	621.75				
							315				315		LF	TEMPORARY TRAFFIC BARRIER	621.90				
							200				200		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							200				200		HR	FLAGGERS	630.15				
							150				150		HR	FLAGGERS, RAILROAD	630.20				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
							25				25		LF	DURABLE 4 INCH WHITE LINE	646.400				
							25				25		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
							8				8		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
							8				8		SF	PAVEMENT MARKING MASK	646.86				
							60				60		SY	GEOTEXTILE UNDER RAILROAD BALLAST	649.21				
									40		40		LB	SEED	651.15				
									300		300		LB	FERTILIZER	651.18				
									2		2		TON	AGRICULTURAL LIMESTONE	651.20				
									2		2		TON	HAYMULCH	651.25				
							1000		14		1014		CY	TOPSOIL	651.35				
									1		1		LS	EPSC PLAN	652.10				
									40		40		HR	MONITORING EPSC PLAN	652.20				
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				