

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	LANDSCAPING	EROSION CONTROL	FULL E.C. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									2800		2800		SY	TEMPORARY EROSION MATTING	653.20				
									1		1		EACH	PREFABRICATED CHECK DAM	653.30				
									10		10		CY	VEHICLE TRACKING PAD	653.35				
									103		103		LF	BARRIER FENCE	653.50				
									560		560		LF	PROJECT DEMARCATION FENCE	653.55				
								1			1		EACH	EVERGREEN SEEDLINGS (PINUS STROBUS)(CONT.)(3' HT.)	656.15				
								13			13		EACH	DECIDUOUS SEEDLINGS (ACER RUBRUM)(CONT.)(5'-6' HT.)	656.16				
								8			8		EACH	DECIDUOUS SEEDLINGS (ACER SACCHARUM)(CONT.)(5'-6' HT.)	656.16				
								12			12		EACH	DECIDUOUS SEEDLINGS (POPULOUS DELTOIDES)(CONT.)(4'-5' HT.)	656.16				
								4			4		EACH	DECIDUOUS SEEDLINGS (PRUNUS SEROTINA)(CONT.)(5'-6' HT.)	656.16				
								24			24		EACH	DECIDUOUS SEEDLINGS (QUERCUS RUBRA)(CONT.)(5'-6' HT.)	656.16				
								7			7		EACH	DECIDUOUS TREES (ACER RUBRUM)(B&B)(1-1/2" CAL.)	656.30				
								7			7		EACH	DECIDUOUS TREES (ACER SACCHARUM)(B&B)(1-1/2" CAL.)	656.30				
								6			6		EACH	DECIDUOUS TREES (QUERCUS RUBRA)(B&B)(1-1/2" CAL.)	656.30				
								80			80		EACH	DECIDUOUS SHRUBS (CORNUS RACEMOSA)(CONT.)(30" HT.)	656.35				
								64			64		EACH	DECIDUOUS SHRUBS (VIBURNUM LENTAGO)(CONT.)(30" HT.)	656.35				
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
							210				210		CY	SPECIAL PROVISION (COARSE AGGREGATE BACKFILL)	900.608				
							30				30		CY	SPECIAL PROVISION (RAILROAD BALLAST)	900.608				
										3000	3000		DL	SPECIAL PROVISION (FIELD OFFICE TELEPHONE)(N.A.B.I.)	900.615				
							24				24		EACH	SPECIAL PROVISION (REMOVAL AND REPLACEMENT OF CROSS TIES)	900.620				
							78				78		LF	SPECIAL PROVISION (REMOVE AND RESET RAILROAD TRACKS)	900.640				
							1				1		LS	SPECIAL PROVISION (TEMPORARY ACCESS ROAD AND STAGING AREAS, SLIDE)	900.645				
									42		42		SY	SPECIAL PROVISION (INSTALL GEOTEXTILE FOR SILT FENCE)	900.675				
							1650				1650		SY	SPECIAL PROVISION (INSTALL GEOTEXTILE UNDER STONE FILL)	900.675				