

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES

TOTALS

DESCRIPTIONS

DETAILED SUMMARY OF QUANTITIES

| SUMMARY OF ESTIMATED QUANTITIES |  |  |  |  |  |  |  |         |                 | TOTALS          |             | DESCRIPTIONS |      |  |             | DETAILED SUMMARY OF QUANTITIES |            |      |  |
|---------------------------------|--|--|--|--|--|--|--|---------|-----------------|-----------------|-------------|--------------|------|--|-------------|--------------------------------|------------|------|--|
|                                 |  |  |  |  |  |  |  | ROADWAY | EROSION CONTROL | FULL C.C. ITEMS | GRAND TOTAL | FINAL        | UNIT | ITEMS  | ITEM NUMBER | ROUND                          | QUANTITIES | UNIT | ITEMS  |
|                                 |  |  |  |  |  |  |  | 1       |                 |                 | 1           |              | LS   | CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS | 201.10      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1000    |                 |                 | 1000        |              | CY   | COMMON EXCAVATION  | 203.15      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1460    |                 |                 | 1460        |              | CY   | UNCLASSIFIED EXCAVATION                                      | 203.17      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 925     |                 |                 | 925         |              | SY   | COLD PLANING, BITUMINOUS PAVEMENT                            | 210.10      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 535     |                 |                 | 535         |              | CY   | SUBBASE OF CRUSHED GRAVEL, COARSE GRADED                     | 301.25      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 3       |                 |                 | 3           |              | CWT  | EMULSIFIED ASPHALT   | 404.85      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 260     |                 |                 | 260         |              | TON  | BITUMINOUS CONCRETE PAVEMENT (FG 58-28)                      | 406.25      | 5                              |            |      | BITUMINOUS CONCRETE PAVEMENT (FG 58-28)      |
|                                 |  |  |  |  |  |  |  | 1       |                 |                 | 1           |              | LS   | FURNISHING EQUIPMENT FOR DRIVING PILING                      | 504.10      | -                              | 102.1      | TON  | TYPE III - TOP COURSE                        |
|                                 |  |  |  |  |  |  |  | 2520    |                 |                 | 2520        |              | LF   | STEEL PILING, HP 10 X 42                                     | 505.10      | -                              | 122.9      | TON  | TYPE III - BOTTOM COURSE                     |
|                                 |  |  |  |  |  |  |  | 40      |                 |                 | 40          |              | HR   | BULLDOZER RENTAL, TYPE I                                     | 608.10      | EST.                           | 5          | TON  | ROUNDING                                     |
|                                 |  |  |  |  |  |  |  | 40      |                 |                 | 40          |              | HR   | ALL PURPOSE EXCAVATOR RENTAL, TYPE I                         | 608.25      | EST.                           | 230        | TON  | TOTAL  |
|                                 |  |  |  |  |  |  |  | 10      |                 |                 | 10          |              | HR   | POWER BROOM RENTAL, TYPE I                                   | 608.30      | EST.                           |            |      | TEMPORARY WORK (FOR INTERIM COMPLETION DATE) |
|                                 |  |  |  |  |  |  |  | 20      |                 |                 | 20          |              | HR   | TRUCK RENTAL   | 608.37      | EST.                           | 100        | CY   | SUBBASE OF CRUSHED GRAVEL, COARSE GRADED     |
|                                 |  |  |  |  |  |  |  | 40      |                 |                 | 40          |              | HR   | LOADER RENTAL, TYPE I  | 608.40      | EST.                           | 30         | TON  | BITUMINOUS CONCRETE PAVEMENT (FG 58-28)      |
|                                 |  |  |  |  |  |  |  | 2770    |                 |                 | 2770        |              | CY   | STONE FILL, TYPE II  | 613.11      | -                              | 480        | LF   | REMOVE AND RESET GUARDRAIL                   |
|                                 |  |  |  |  |  |  |  | 456     |                 |                 | 456         |              | LF   | STEEL BEAM GUARDRAIL, GALVANIZED                             | 621.20      | -                              | 100        | LF   | ADJUST HEIGHT OF GUARD RAIL                  |
|                                 |  |  |  |  |  |  |  | 1       |                 |                 | 1           |              | EACH | MANUFACTURED TERMINAL SECTION, FLARED                        | 621.50      | -                              | 550        | LF   | TEMPORARY TRAFFIC BARRIER                    |
|                                 |  |  |  |  |  |  |  | 2       |                 |                 | 2           |              | EACH | ENERGY ABSORPTION ATTENUATOR                                 | 621.56      | -                              | 640        | LF   | TEMPORARY 4 INCH WHITE LINE                  |
|                                 |  |  |  |  |  |  |  | 490     |                 |                 | 490         |              | LF   | REMOVE AND RESET GUARDRAIL                                   | 621.75      | -                              | 555        | LF   | TEMPORARY 4 INCH WHITE LINE, PAINT           |
|                                 |  |  |  |  |  |  |  | 100     |                 |                 | 100         |              | LF   | ADJUST HEIGHT OF GUARDRAIL                                   | 621.79      | EST.                           | 1105       | LF   | TEMPORARY 4 INCH YELLOW LINE, PAINT          |
|                                 |  |  |  |  |  |  |  | 1100    |                 |                 | 1100        |              | LF   | TEMPORARY TRAFFIC BARRIER                                    | 621.90      | -                              | 24         | LF   | TEMPORARY 24 INCH STOP BAR                   |
|                                 |  |  |  |  |  |  |  | 200     |                 |                 | 200         |              | HR   | UNIFORMED TRAFFIC OFFICERS                                   | 630.10      | EST.                           | 330        | SF   | REMOVAL OF EXISTING PAVEMENT MARKINGS        |
|                                 |  |  |  |  |  |  |  | 500     |                 |                 | 500         |              | HR   | FLAGGERS   | 630.15      | EST.                           | 550        | SF   | PAVEMENT MARKING MASK                        |
|                                 |  |  |  |  |  |  |  |         |                 | 1               | 1           |              | LS   | FIELD OFFICE, ENGINEERS                                      | 631.10      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  |         |                 | 1               | 1           |              | LS   | TESTING EQUIPMENT, BITUMINOUS                                | 631.17      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  |         |                 | 1               | 1           |              | LU   | FIELD OFFICE TELEPHONE (N.A.B.U.)                            | 631.25      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1       |                 |                 | 1           |              | LS   | MOBILIZATION/DEMobilIZATION                                  | 635.11      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1       |                 |                 | 1           |              | LS   | TRAFFIC CONTROL  | 641.10      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 555     |                 |                 | 555         |              | LF   | DURABLE 4 INCH WHITE LINE                                    | 646.400     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1105    |                 |                 | 1105        |              | LF   | DURABLE 4 INCH YELLOW LINE                                   | 646.410     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1680    |                 |                 | 1680        |              | LF   | TEMPORARY 4 INCH WHITE LINE                                  | 646.600     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 555     |                 |                 | 555         |              | LF   | TEMPORARY 4 INCH WHITE LINE, PAINT                           | 646.602     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1105    |                 |                 | 1105        |              | LF   | TEMPORARY 4 INCH YELLOW LINE, PAINT                          | 646.612     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 48      |                 |                 | 48          |              | LF   | TEMPORARY 24 INCH STOP BAR                                   | 646.680     | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 21      |                 |                 | 21          |              | EACH | LINE STRIPING TARGETS  | 646.76      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 880     |                 |                 | 880         |              | SF   | REMOVAL OF EXISTING PAVEMENT MARKINGS                        | 648.85      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 1100    |                 |                 | 1100        |              | SF   | PAVEMENT MARKING MASK  | 648.86      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  | 680     |                 |                 | 680         |              | SY   | GEOTEXTILE FOR ROADBED SEPARATOR                             | 649.11      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  |         | 2150            |                 | 2150        |              | SY   | GEOTEXTILE UNDER STONE FILL                                  | 649.31      | -                              |            |      |  |
|                                 |  |  |  |  |  |  |  |         | 105             |                 | 105         |              | SY   | GEOTEXTILE FOR SILT FENCE                                    | 649.51      | -                              |            |      |  |

REVISED: 09/28/07

PROJECT NAME: **WOLCOTT**  
 PROJECT NUMBER: **STP 030-2(22)**

PROJECT MANAGER: **MBL**      DRAWN BY: **MBL**  
 DESIGNED BY: **MBL**              CHECKED BY: **SDM**  
 QUANTITY SHEET #1              SHEET 7 OF 22