

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES							TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	ROADWAY (NO FEDERAL/STATE)	LANDSCAPING (NO FEDERAL/STATE)	EROSION CONTROL	EROSION CONTROL (NO FEDERAL/STATE)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	2						2		EACH	PRECAST REINFORCED CONCRETE MANHOLE WITH CAST IRON COVER (10' DIA. ) (> 25 FOOT DEPTH)	604.21	-			
	1						1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-			
	20						20		MGAL	DUST CONTROL WITH WATER	609.10	4			
				40			40		CY	STONE FILL, TYPE I	613.10	2			
				70			70		CY	STONE FILL, TYPE II	613.11	3			
	150						150		LF	TREATED TIMBER CURB	616.35	28			
	30						30		LF	REMOVING AND RESETTING CURB	616.40	4			
	9						9		EACH	YIELDING MARKER POSTS	619.17	-			
	45						45		LF	CHAIN-LINK FENCE, 4 FEET	620.11	4			
	70						70		LF	REMOVING AND RESETTING FENCE	620.50	5			
	275						275		LF	REMOVE AND RESET GUARDRAIL	621.75	25			
	300						300		LF	TEMPORARY TRAFFIC BARRIER	621.90	38			
	300						300		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	46			
	40						40		LF	PVC SEWER PIPE (8")	628.35	1.5			
	1						1		LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42	-			
	70						70		LF	DUCTILE IRON PIPE, CEMENT-LINED (12")	629.24	4			
	1						1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42	-			
	850	100					950		TON	CRUSHED STONE BEDDING	629.54	35			
	128						128		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
	400						400		HR	FLAGGERS	630.15	EST			
						1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
						3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
	1						1		LS	MOBILIZATION/DEMobilIZATION (PARTICIPATING)	635.11	-			
	1						1		LS	TRAFFIC CONTROL	641.10	-			
	120						120		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17	EST			
	700						700		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	33			
	1100						1100		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	16			
	300						300		LF	DURABLE 6 INCH YELLOW LINE, THERMOPLASTIC	646.432	12			
	3000						3000		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	18			
	3250						3250		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	10			
	1050						1050		LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	42			
	40						40		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	4			
	560						560		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	7			
	680						680		SF	PAVEMENT MARKING MASK	646.86	1			
				1550			1550		SY	GEOTEXTILE UNDER STONE FILL	649.31	49			
				50			50		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	14			
				25	25		50		LB	SEED	651.15	37			
				25	25		50		LB	SEED, WINTER RYE	651.17	37			
				50	50		100		LB	FERTILIZER	651.18	46			
				0.2	0.1		0.3		TON	AGRICULTURAL LIMESTONE	651.20	0.09			

PROJECT NAME: PERU  
PROJECT NUMBER: STP SCR(4)

FILE NAME: z07bi06qty.dgn  
PROJECT LEADER: E. ATKINS  
DESIGNED BY: M. BRADLEY  
QUANTITY SHEET 2

PLOT DATE: 12/31/2014  
DRAWN BY: M. BRADLEY  
CHECKED BY: E. ATKINS  
SHEET 22 OF 45