

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES						TOTALS	DESCRIPTIONS	ITEM NO.	ROUND
ALTERNATE A ROADWAY	ALTERNATE B ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	ROADWAY	GRAND TOTAL	UNIT	ITEMS		
			1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			1		1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				1	1	LS	TRAFFIC CONTROL	641.10	-
				2	2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
				101100	101100	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	156
				90200	90200	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	139
				345	345	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	3
				96	96	EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				100	100	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	5
				101100	101100	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	156
				90200	90200	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	139
				345	345	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	3
				96	96	EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
				100	100	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	5
				5300	5300	EACH	LINE STRIPING TARGETS	646.76	28
		1360			1360	SY	GEOTEXTILE UNDER STONE FILL	649.31	7.4
		36			36	LB	SEED	651.15	EST.
		295			295	LB	FERTILIZER	651.18	EST.
		1.3			1.3	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		70			70	CY	TOPSOIL	651.35	EST.
		7600			7600	SY	TEMPORARY EROSION MATTING	653.20	43
				413	413	SF	TRAFFIC SIGNS, TYPE A	675.20	0.73
				1400	1400	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	5
				108	108	EACH	REMOVING SIGNS	675.50	-
				14	14	EACH	ERECTING SALVAGED SIGNS	675.60	-
				40	40	EACH	DELINEATOR WITH STEEL POST	676.10	-
				36	36	EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-
				27	27	EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	-
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				2080	2080	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES) END ITEMS COMMON TO ALL ALTERNATES	900.675	23
							BEGIN ALTERNATE A		
20050					20050	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	189
	1				1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	1				1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
	1				1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
	1				1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.) END ALTERNATE A	490.34	-

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
14,260	TON	MAINLINE WEARING COURSE (TYPE IVS)
398	TON	SIDEROADS (TYPE IVS)
308	TON	PULLOUTS (TYPE IVS)
5	TON	BRIDGES (TYPE IVS)
4890	TON	LEVELING (TYPE IVS)
189	TON	ROUNDING
20,050	TON	TOTAL
		GEOTEXTILE UNDER STONE FILL
880	SY	DITCH CLEANING
472.6	SY	SLOPE REPAIR
7.4	SY	ROUNDING
1360	SY	TOTAL
		TEMPORARY EROSION MATTING
4132	SY	DITCH CLEANING
625	SY	M.T.S. CONSTRUCTION
2420	SY	SEED PROTECTION
380	SY	EXCAVATION OF SURFACES AND PAVEMENTS
43	SY	ROUNDING
7600	SY	TOTAL

PROJECT NAME:	SHELDON-ENOSBURG	
PROJECT NUMBER:	STP 2714(I)	
FILE NAME:	p07b180.dgn	PLOT DATE:
PROJECT LEADER:	JLL	07-NOV-2011 16:46
DESIGNED BY:	STANTEC	DRAWN BY:
IPARM FILE:	p07b180qs02.i	CHECKED BY:
		JLL
		SHEET 5 OF 29