STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 07

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 105											OPTION ITEMS																									
ENOSBURG (CONT.)																																				
0.097, LT	ORCHARD ST STOP 1050 0603 0010 B-B	1 1	30 6	30 10	6.25 0.42		1				1					X		X															SIGN ID CODE RI-1 (T.H. 8) INSTALL STREET SIGN 90 DEGREES AND 6 INCHES ABOVE STOP SIGN. INSTALL MM PLAQUE BACK TO BACK WITH STOP SIGN		E-143 E-138
0.105, LT	LEGAL LOAD LIMIT 24,000 POUNDS SPEED LIMIT 25	1 1	24 24	30 30	5.00 5.00						1					X		X															SIGN ID CODE VR-017 (T.H. 8) SIGN ID CODE R2-1 (T.H. 8)		E-141 E-142
0.191, LT	CENTER RUMBLE STRIPS NEXT 6 MILES	1 1	30 24	30 18	6.25 3.00						1					X		X																27 27	
0.289, RT	BRIDGE 17 VT 105	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
0.299, RT	STOP	1	30	30	6.25						1					X		X															SIGN ID CODE RI-1 (T.H. 7)		E-143
0.300, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-017 (T.H. 7) INSTALL LEGAL LOAD LIMIT SIGN BEYOND DRIVE ALONG ST. ALBANS STREET		E-141
0.306, LT	BRIDGE 17 VT 105	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
0.307, RT	PEARL ST VT 105W ST. ALBANS ST STOP 1050 0603 0031 B-B	1 1 1	30 6	30 10	6.25 0.42		1 1				1					X		X															SIGN ID CODE RI-1 (T.H. 7) PLACE MM PLAQUE BACK TO BACK WITH STOP SIGN INSTALL SALVAGED STREET SIGNS 90 DEGREES TO EACH OTHER AND 6 INCHES ABOVE STOP SIGN		E-143 E-138
0.321, LT	RECREATION TRAIL ALL SEASON	1 1	30 18	30 24	6.25 3.00						2					X		X															SIGN ID CODE VW-622	22	E-154
0.234, LT	STOP	1	30	30	6.25											X																			
TOTALS					SF 53.75	SF	EA. 3	SF				FT	FT	FT	FT 30	FT 120	FT 150		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE HIGHWAY SAFETY AND DESIGN SECTION'S "SIGN POST DESIGN GUIDELINE."

Stantec

PROJECT NAME: SHELDON-ENOSBURG
PROJECT NUMBER: STP 2714(I)

FILE NAME: p07b180.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07b180tss07.i
PLOT DATE: 07-NOV-2011 16:46
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 20 OF 29