STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 08

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 105											OPTION ITEMS																									
ENOSBURG (CONT.) 0.423, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X																SIGN ID CODE VR-017 (CENTER STREET)		E-141
~~0.430, RT~~ 0.423, RT	STOP 1050 0603 0043 B-B	1 1	30 6	30 10	6.25 0.42						1					X		X																SIGN ID CODE RI-1 (CENTER STREET) PLACE MM PLAQUE BACK TO BACK WITH STOP SIGN		E-143 E-138
0.450, LT	SPEED LIMIT 35 STATE HIGHWAY BEGINS	1 1	24 24	30 18	5.00 3.00						1					X		X																SIGN ID CODE R2-1 SIGN ID CODE VR-038		E-142 E-141
	SHEET TOTAL				19.67											45																			
	TSS SHEET 1 SUBTOTALS				67.60		2								15	210																			
	TSS SHEET 2 SUBTOTALS				39.60		3								30																			
	TSS SHEET 3 SUBTOTALS				61.21		5									180																			
	TSS SHEET 4 SUBTOTALS				73.10		-								15	165																			
	TSS SHEET 5 SUBTOTALS				59.34		1								30	195																			
	TSS SHEET 6 SUBTOTALS				38.00		-								90	90																			
	TSS SHEET 7 SUBTOTALS				53.75		3								30	120																			
	TSS SHEET 8 SUBTOTALS				19.67		-								-	45																			
	PROJECT SUBTOTALS				412.27		14								210	1185																			
	ROUNDING				0.73		-									5																			
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB							
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE HIGHWAY SAFETY AND DESIGN SECTION'S "SIGN POST DESIGN GUIDELINE."	**TOTALS**		SF 413	SF	EA. 14	SF						FT			FT 1400					LB			EA.	LB				EA.	EA.	LB				

Stantec

PROJECT NAME: SHELDON-ENOSBURG
PROJECT NUMBER: STP 2714(1)

FILE NAME: p07b180.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07b180tss08.i

PLOT DATE: 07-NOV-2011 16:46
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 21 OF 29