SIGN REMOVAL TABLE

SHELDON VT ROUTE 105

STATION (MM)	LT/RT	675.50 EA.	675.60 EA.	LOCATION	SIGN TYPE
2.375	LT	1		MILL STREET (TH 43)	STOP
2.375	LT	1		MILL STREET (TH 43)	MM PLAQUE
2.381	LT	1		MILL STREET (TH 43)	LEGAL LOAD LIMIT
2.579	RT	2		VT ROUTE 105	RECREATION TRAIL / ALL SEASON
2.608	RT	1		VT ROUTE 105	MM PLAQUE
2.648	RT	1	1	VT ROUTE 105	SPEED LIMIT
2.652	LT	1	1	VT ROUTE 105	SPEED LIMIT
2.748	RT	1		SWEET HOLLOW ROAD (TH 28)	LEGAL LOAD LIMIT
2.749	LT	1		SHAWVILLE ROAD (TH 28)	STOP
2.749	LT	1		SHAWVILLE ROAD (TH 28)	MM PLAQUE
2.754	LT	1		SHAWVILLE ROAD (TH 28)	LEGAL LOAD LIMIT
2.754	LT	1		SHAWVILLE ROAD (TH 28)	CHILDREN AT PLAY •
2.755	RT	1		SWEET HOLLOW ROAD (TH 28)	STOP
2.755	RT	1		SWEET HOLLOW ROAD (TH 28)	MM PLAQUE
3.009	LT	1		MILL STREET (TH 1)	STOP
3.009	LT	1		MILL STREET (TH 1)	LEGAL LOAD LIMIT
3.009	LT	1		MILL STREET (TH 1)	MM PLAQUE
3.144	RT	1		POOR FARM ROAD (TH 29)	LEGAL LOAD LIMIT
3.153	RT	1		POOR FARM ROAD (TH 29)	STOP
3.153	RT	1		POOR FARM ROAD (TH 29)	MM PLAQUE
3.351	LT	1	1	VT ROUTE 105	SPEED LIMIT
3.392	LT	1		VT ROUTE 105	SHELDON SPRINGS / ST ALBANS 10
3.426	LT	1		VT ROUTE 105	MM PLAQUE
3.451	LT	1	1	VT ROUTE 105	SPEED LIMIT WARNING
3.628	LT	1		BERGERON ROAD (TH 21)	STOP
3.628	LT	1		BERGERON ROAD (TH 21)	MM PLAQUE
3.630	RT	1		VT ROUTE 105	MM PLAQUE
3.635	LT	1		BERGERON ROAD (TH 21)	LEGAL LOAD LIMIT
3.664	RT	1	1	VT ROUTE 105	T.I.S.
3.883	RT	1		MAIN STREET (TH 4)	STOP
3.883	RT	1		MAIN STREET (TH 4)	MM PLAQUE
4.241	LT	1		CLARK ROAD (TH 47)	STOP
4.241	RT	1		SEVERANCE ROAD (TH 41)	LEGAL LOAD LIMIT
4.241	RT	1		SEVERANCE ROAD (TH 41)	MM PLAQUE
4.248	LT	1		CLARK ROAD (TH 47)	LEGAL LOAD LIMIT
4.249	RT	1		SEVERANCE ROAD (TH 41)	STOP
4.249	RT	1		SEVERANCE ROAD (TH 41)	MM PLAQUE
SUBTOTALS		38	5		

SHELDON VT ROUTE 105 (CONT.)

STATION (MM)	LT/RT	675.50 EA.	675.60 EA.	LOCATION	SIGN TYPE
4.417	LT	1		VT ROUTE 78	STOP
4.417	LT	1		VT ROUTE 78	MM PLAQUE
4.434	LT	1		VT ROUTE 78	STOP
4.434	LT	1		VT ROUTE 78	MM PLAQUE
4.524	LT	4	4	VT ROUTE 105	DESTINATION BOARDS
4.573	LT	2		VT ROUTE 105	ROUTE MARKERS
4.672	RT	1	1	CASINO ROAD (TH 40)	STREET SIGN
4.673	RT	1		CASINO ROAD (TH 40)	LEGAL LOAD LIMIT
4.684	RT	1		CASINO ROAD (TH 40)	STOP
4.684	RT	1		CASINO ROAD (TH 40)	MM PLAQUE
4.723	LT	1		SHELDON HEIGHTS (TH 52)	STOP
4.730	LT	1		SHELDON HEIGHTS (TH 52)	LEGAL LOAD LIMIT
4.954	LT	1		DANYOW ROAD (TH 39)	STOP
4.960	LT	1		DANYOW ROAD (TH 39)	LEGAL LOAD LIMIT
4.960	LT	1		DANYOW ROAD (TH 39)	STOP
4.961	LT	1		DANYOW ROAD (TH 39)	STOP
5.177	LT	1		VT ROUTE 105	CURVE / SIDE ROAD WARNING
5.211	RT	1		VT ROUTE 105	MM PLAQUE
5.240	LT	1		DANYOW ROAD (TH 39)	STOP
5.246	LT	1		DANYOW ROAD (TH 39)	LEGAL LOAD LIMIT
5.246	LT	1		DANYOW ROAD (TH 39)	MM PLAQUE
6.707	LT	1		VT ROUTE 120	STOP
6.707	LT	1		VT ROUTE 120	MM PLAQUE
6.707	RT	1		KANE ROAD (TH 3)	LEGAL LOAD LIMIT
6.715	RT	1		KANE ROAD (TH 3)	STOP
7.170	RT	1		VT ROUTE 105	PARKING
7.190	RT	1	1	VT ROUTE 105	MEMORIAL HIGHWAY PLAQUE
7.200	RT	1		VT ROUTE 105	$500 FINE
7.229	LT	1		VT ROUTE 105	PARKING
7.244	RT	1		VT ROUTE 105	MM PLAQUE
7.262	LT	2		VT ROUTE 105	RECREATION TRAIL / ALL SEASON
8.717	LT	1		VT ROUTE 236	STOP
8.717	LT	1		VT ROUTE 236	MM PLAQUE
9.133	RT	1		VT ROUTE 105	ARROW
9.148	RT	1		VT ROUTE 105	ARROW
9.177	LT	1		VT ROUTE 105	BRIDGE PLAQUE
9.223	RT	2		VT ROUTE 105	RECREATION TRAIL / ARROW
10.041	RT	1		VT ROUTE 105	BRIDGE PLAQUE
SUBTOTALS		44	6		

SHELDON VT ROUTE 105 (CONT.)

STATION (MM)	LT/RT	675.50 EA.	675.60 EA.	LOCATION	SIGN TYPE
10.047	LT	1		VT ROUTE 105	BRIDGE PLAQUE
10.066	LT	1		VT ROUTE 105	MM PLAQUE
10.391	LT	1		COLTON ROAD (TH 8)	STOP
10.391	LT	1		COLTON ROAD (TH 8)	MM PLAQUE
10.406	LT	1		COLTON ROAD (TH 8)	LEGAL LOAD LIMIT
10.600	RT	1		VT ROUTE 105	BRIDGE PLAQUE
10.610	LT	1		VT ROUTE 105	BRIDGE PLAQUE
10.669	LT	1		VT ROUTE 105	MM PLAQUE
ENOSBURG VT ROUTE 105					
0.091	LT	1		ORCHARD STREET (TH 8)	STOP
0.097	LT	1		ORCHARD STREET (TH 8)	STOP
0.097	LT	1	1	ORCHARD STREET (TH 8)	STREET SIGN
0.105	LT	1		ORCHARD STREET (TH 8)	LEGAL LOAD LIMIT
0.105	LT	1		ORCHARD STREET (TH 8)	SPEED LIMIT
0.289	RT	1		VT ROUTE 105	BRIDGE PLAQUE
0.299	RT	1		ST. ALBANS STREET (TH 7)	LEGAL LOAD LIMIT
0.299	RT	1		ST. ALBANS STREET (TH 7)	STOP
0.306	LT	1		VT ROUTE 105	BRIDGE PLAQUE
0.307	RT	1		ST. ALBANS STREET (TH 7)	STOP
0.307	RT	1	1	ST. ALBANS STREET (TH 7)	STREET SIGN
0.307	RT	1	1	ST. ALBANS STREET (TH 7)	STREET SIGN
0.321	LT	2		VT ROUTE 105	RECREATION TRAIL/ALL SEASON
0.423	RT	1		CENTER STREET	LEGAL LOAD LIMIT
0.423	RT	1		CENTER STREET	STOP
0.450	LT	2		VT ROUTE 105	SPEED LIMIT/STATE HIGHWAY BEGINS
SUBTOTAL		26	3		
COLUMN 1		38	5		
COLUMN 2		44	6		
COLUMN 3		26	3		
TOTAL		108	14		

• - RETURN SIGN TO TOWN OF SHELDON

Stantec

SIGN REMOVAL LOCATION SHEET

PROJECT NAME: SHELDON-ENOSBURG
PROJECT NUMBER: STP 2714(1)

FILE NAME: p07b180.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07b180srl.i

PLOT DATE: 07-NOV-2011 16:46
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 23 OF 29