QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		FULL CE	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				1	1	EA	THINNING AND TRIMMING FOR SIGNS	201.31	-
				1	1	CY	COMMON EXCAVATION	203.15	0.1
				2	2	CY	SOLID ROCK EXCAVATION	203.16	0.86
				1375	1375	CY	EARTH BORROW	203.30	-
				1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
				20500	20500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	287.4
				5000	5000	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	20.7
				1800	1800	TON	AGGREGATE SHOULDERS, RAP	402.13	13
				1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
				20000	20000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	300.7
				1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				1	1	LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
				1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
				1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
			130		130	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	4
			175		175	LF	REMOVAL OF EXISTING RAILING	525.10	-
			175		175	LF	BRIDGE RAILING REPAIR, TYPE II	525.55	-
			100		100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
				18	18	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
				4	4	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
				310	310	HR	POWER GRADER RENTAL	608.15	EST
				580	580	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
				230	230	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
				110	110	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
				1160	1160	HR	TRUCK RENTAL	608.37	EST
				30	30	HR	LOADER RENTAL, TYPE I	608.40	EST
				900	900	CY	STONE FILL, TYPE I	613.10	10
				10	10	LF	BITUMINOUS CONCRETE CURB, TYPE A	616.305	-
				725	725	LF	TREATED TIMBER CURB	616.35	-
				10	10	LF	REMOVAL OF EXISTING CURB	616.41	-
				105	105	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1
				6	6	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	0.44

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
20212.6	SY	VT ROUTE 104
287.4	SY	ROUNDING
20500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (TYPE IVS)
		WEARING COURSE
13404.9	TON	TYPE IVS
303.1	TON	TOWN HIGHWAYS
617.7	TON	PULL OFFS
900.0	TON	SPOT LEVELING
		LEVELING COURSE
4473.6	TON	TYPE IVS
300.7	TON	ROUNDING
20000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CAMBRIDGE-FAIRFAX
PROJECT NUMBER: STP 2713(I)

FILE NAME: p07B182.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #1

PLOT DATE: 29-DEC-2014 13:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 12 OF 36