QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY NON-FEDERAL PARTICIPATING	FULL CE	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			8	8	SF	DETECTABLE WARNING SURFACE	618.30	-
			116	116	EA	YIELDING MARKER POSTS	619.17	-
			7125	7125	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	0.5
			9500	9500	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	38.25
			130	130	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215	-
			54	54	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
			18	18	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			4	4	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	-
			18725	18725	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	18.75
4				4	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
			300	300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
			2500	2500	HR	FLAGGERS	630.15	EST
	1			1	LS	FIELD OFFICE, ENGINEERS	631.10	-
	1			1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
	3000			3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
			1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			1	1	LS	TRAFFIC CONTROL	641.10	-
			4	4	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
						BEGIN OPTION AA		
			94000	94000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1714
			94000	94000	LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	1714
			94000	94000	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	1714
						END OPTION AA		
						BEGIN OPTION BB		
			80000	80000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	2104
			80000	80000	LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413	2104
			80000	80000	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	2104
						END OPTION BB		
						BEGIN OPTION CC		
			470	470	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	21
			470	470	LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483	21
			470	470	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	21
						END OPTION CC		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CAMBRIDGE-FAIRFAX
PROJECT NUMBER: STP 2713(I)

FILE NAME: p07B182.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #2

PLOT DATE: 29-DEC-2014 13:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 13 OF 36