QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		FULL CE	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN OPTION DD		
				69	69	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				69	69	EA	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493	-
				69	69	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
							END OPTION DD		
				95000	95000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	2714
				80000	80000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	2104
				470	470	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	21
				69	69	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
				4350	4350	EA	LINE STRIPING TARGETS	646.76	95
				4100	4100	SY	GEOTEXTILE UNDER STONE FILL	649.31	95
				115	115	LB	SEED	651.15	2.7
				750	750	LB	FERTILIZER	651.18	47
				3	3	TON	AGRICULTURAL LIMESTONE	651.20	0.2
				7	7	TON	HAY MULCH	651.25	-
				1120	1120	CY	TOPSOIL	651.35	14
				8700	8700	SY	TEMPORARY EROSION MATTING	653.20	88
				70	70	EA	DELINEATOR WITH STEEL POST	676.10	EST
				70	70	EA	REMOVAL OF EXISTING DELINEATOR	676.12	EST
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				3300	3300	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	104.8
				50	50	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE 1)	900.680	EST
				1100	1100	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	16

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		TOPSOIL
350		ITEM DETAIL SUMMARY SHEET
756		FROM DITCHING AREA
14		ROUNDING
1120		TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CAMBRIDGE-FAIRFAX
PROJECT NUMBER: STP 2713(1)

FILE NAME: p07B182.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #3

PLOT DATE: 29-DEC-2014 13:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 14 OF 36