STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 2

BEGIN STATION	END STATION	POS.	201.31 THINNING/ TRIMMING FOR SIGNS	203.30 EARTH BORROW	402.13 AGG. SHOULD. RAP	525.10 REMOVAL OF EXIST. RAILING	525.55 BRIDGE RAILING REPAIR TYPE II	604.412 REHAB. D.I. CLASS I	604.415 REHAB. D.I. CLASS II		616.35 TREATED TIMBER CURB	616.47 BIT. CONC. GUTTERS AND TRAF. ISLANDS	619.17 YIELDING MARKER POSTS	621.20 STEEL BEAM G.R., GALV	621.205 STEEL BEAM G.R. GALV. W/8FT POSTS	621.215 H.D. STEEL BEAM G.R. GALV. W/8FT POSTS	621.50 MANUF. TERMINAL SECTION, FLARED	621.60 ANCHOR FOR S.B. G.R.	621.70 G.R. APPRCH SECTION GALV. TYPE I	621.80 REMOVE & DISP. OF G.R.	629.20 ADJUST ELEV. VALVE BOX	651.35 TOPSOIL	676.10 DEL IN. WITH STEEL POSTS	676.12 REMOVAL OF EXIST. DEL IN.	REMARKS
			EACH	CY	TON	LF	LF	EACH	EACH		LF	TON	EACH	LF	LF	LF	EACH	EACH	EA	LF	EACH	CY	EACH	EACH	
21+72	24+72	RT		50											~~225~~		~~2~~ 1	1		300		10	2	2	INSTALL FLARED MTS @ STA. 21+72 AND
															262.5										STA. 24+34.5
22+13	26+50.5	LT		50											362.5		2			437.5		10	2	2	INSTALL FLARED MTS @ STA. 22+13 AND
																									STA. 26+13
30+18.5	34+68.5	RT		50		87.5	87.5					NOTE: 35' MORE OF 621.215			~~237.5~~	~~65~~	2			362.5		10	2	2	INSTALL FLARED MTS @ STA. 30+18.5 AND
												AND 35' LESS OF 621.205			202.5	100									STA. 34+31
30+18.5	33+43.5	LT		50		87.5	87.5								~~112.5~~	~~65~~	2			237.5		10	2	2	INSTALL FLARED MTS @ STA. 30+18.5 AND
															77.5	100									STA. 33+06
78+87	87+49.5	LT		50											787.5		2			862.5		10	2	2	INSTALL FLARED MTS @ STA. 78+87 AND
																									STA. 87+12
79+03	82+53	RT		25											314.5		1	1		350		10	2	2	INSTALL FLARED MTS @ STA. 79+03 AND 12'-6"
																									LONG, 16' RADIUS WITH ANCHOR @ STA. 82+53
82+88	88+13	RT		25											489.5		1	1		525		10	2	2	INSTALL 12'-6" LONG, 16' RADIUS WITH ANCHOR
																									@ STA. 82+88 AND FLARED MTS @ STA. 87+75.5
90+20	101+45	RT		50											1075 + 30'		2			1125		10	2	2	INSTALL FLARED MTS @ STA. 90+20 AND
															FOR DOUBLE SPACING										STA. 101+07.5
133+72.5	136+22.5	LT		25											214.5		1	1		250		10	2	2	INSTALL FLARED MTS @ STA. 133+72.5 AND 12'-6"
																									LONG, 16' RADIUS WITH ANCHOR @ STA. 136+22.5
134+22	139+47	RT		50											450		2			525		10	2	2	INSTALL FLARED MTS @ STA. 134+22 AND
																									STA. 139+09.5
136+52	145+52	LT		25										864.5			1	1		887.5		10	2	2	INSTALL 12'-6" LONG, 16' RADIUS WITH ANCHOR
																									@ STA. 136+52 AND FLARED MTS @ STA. 145+14.5
142+29	145+91.5	RT		25										327			1	1		325		10	2	2	INSTALL FLARED MTS @ STA. 142+29 AND 12'-6"
																									LONG, 16' RADIUS WITH ANCHOR @ STA. 145+91.5
148+81	159+18.5	RT		25										502	500		1	1		1012.5		10	2	2	INSTALL 12'-6" LONG, 16' RADIUS WITH ANCHOR @
																									STA. 148+81 AND FLARED MTS @ STA. 158+81
153+56	156+06	LT		50											175		2			250		10	2	2	INSTALL FLARED MTS @ STA. 153+56 AND
																									STA. 155+68.5
160+05	183+80	RT		25										2337.5			1			2375		5	1	1	INSTALL FLARED MTS @ STA. 160+05, CONNECT
																									TO EXISTING GUARDRAIL AT STA. 183+80
SUBTOTAL			-	575	-	175	175	-	-		-	-	-	4031	~~4943.5~~	~~130~~	~~23~~	~~6~~	-	9825	-	145	29	29	
															4941	200	22	7							

ITEM DETAIL SUMMARY SHEET 2

PROJECT NAME: CAMBRIDGE-FAIRFAX
PROJECT NUMBER: STP 2713(I)

FILE NAME: p07I182.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: p07I182_16.i

PLOT DATE: 29-DEC-2014 13:46
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 16 OF 36