

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
								850			850		CY	COMMON EXCAVATION	203.15	14			
								130			130		CY	TRENCH EXCAVATION OF EARTH	204.20	5			
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								550			550		CY	STRUCTURE EXCAVATION	204.25	6			
								6			6		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	0.7			
								1450			1450		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	50			
														BEGIN OPTION AA					
								530			530		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25	11			
								530			530		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	11			
														END OPTION AA					
								6			6		CWT	EMULSIFIED ASPHALT	404.65	0.4			
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
								60			60		LF	18" CPEP	601.0915	-			
								1			1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18	-			
								225			225		LF	6 INCH UNDERDRAIN PIPE	605.10	-			
								188			188		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	-			
								3			3		EACH	UNDERDRAIN FLUSHING BASIN	605.95	-			
								3			3		HR	POWER GRADER RENTAL	608.15	2			
								10			10		HR	POWER BROOM RENTAL, TYPE I	608.30	EST			
								1			1		MGAL	DUST CONTROL WITH WATER	609.10	EST			
								190			190		CY	STONE FILL, TYPE I	613.10	6			
								340			340		CY	STONE FILL, TYPE II	613.11	10			
								250			250		LF	TREATED TIMBER CURB	616.35	-			
								6			6		EACH	YIELDING MARKER POSTS	619.17	-			
								2			2		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			
								250			250		LF	REMOVE AND RESET GUARDRAIL	621.75	EST			
								875			875		LF	TEMPORARY TRAFFIC BARRIER	621.90	EST			
								40			40		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
								400			400		HR	FLAGGERS	630.15	EST			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								1			1		LS	TRAFFIC CONTROL	641.10	-			
								2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								900			900		LF	4 INCH WHITE LINE	646.20	-			
								1910			1910		LF	4 INCH YELLOW LINE	646.21	-			
								875			875		LF	TEMPORARY 4 INCH WHITE LINE, TYPE II TAPE	646.601	-			
								1910			1910		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	-			
								318			318		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST			
									30		30		LB	SEED	651.15	EST			

QUANTITY SHEET 1

PROJECT NAME:	CAMBRIDGE	PLOT DATE:	06-AUG-2009
PROJECT NUMBER:	STP 0235(9)	DRAWN BY:	N. PAPPAS
FILE NAME:	d087c152_frm.DGN	CHECKED BY:	S. MENARD
PROJECT LEADER:	K. ROBIE	SHEET	6 OF 28
DESIGNED BY:	N. PAPPAS		
IPARM:	d07x152_qty_011		