

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									250		250		LB	FERTILIZER	651.18	EST			
									1		1		TON	AGRICULTURAL LIMESTONE	651.20	EST			
									1		1		TON	HAY MULCH	651.25	EST			
									135		135		CY	TOPSOIL	651.35	EST			
									1		1		LS	EPSC PLAN	652.10	EST			
									20		20		HR	MONITORING EPSC PLAN	652.20	EST			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
									1500		1500		SY	TEMPORARY EROSION MATTING	653.20	56			
									1700		1700		LF	PROJECT DEMARCATION FENCE	653.55	150			
								2			2		EACH	REMOVING SIGNS	675.50	-			
								2			2		EACH	ERECTING SALVAGED SIGNS	675.60	-			
								2			2		EACH	SETTING SALVAGED POSTS	675.61	-			
								1			1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40	-			
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
								200			200		LF	SPECIAL PROVISION (8" UNDERDRAIN PIPE)	900.640				
								85			85		LF	SPECIAL PROVISION (HORIZONTAL DIRECTIONAL DRILLING)(12" STEEL CASING W/8" CAR	900.640				
								1			1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650	-			
								1			1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650	-			
									170		170		SY	SPECIAL PROVISION (INSTALL GEOTEXTILE FOR SILT FENCE)	900.675	3			
								2550			2550		SY	SPECIAL PROVISION (INSTALL GEOTEXTILE UNDER STONE FILL)	900.675	4			
								550			550		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	4			