QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL E&C	EROSION CONTROL	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			1000	1000	CY	EARTH BORROW	203.30	50
			1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			18500	18500	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	392
			4000	4000	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	159
			500	500	TON	AGGREGATE SHOULDERS	402.12	81
			1981	1981	TON	AGGREGATE SHOULDERS, RAP	402.13	-
			775	775	CWT	EMULSIFIED ASPHALT	404.65	21
			1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
						BEGIN OPTION AA		
			24000	24000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	306
						(0% RAP CONTENT)		
			24000	24000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	306
						(0% < RAP CONTENT < 15.0%)		
			24000	24000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	306
						(15.0% <= RAP CONTENT < 25.0%)		
			24000	24000	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	306
						(25.0% <= RAP CONTENT <= 50.0%)		
						END OPTION AA		
			1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
			1	1	LU	MAT. DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
			1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
			1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
		50		50	LF	BRIDGE RAILING REPAIR, TYPE I	525.50	-
			3	3	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
			1	1	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
			1	1	EA	REHAB DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
			1	1	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
			150	150	HR	POWER GRADER RENTAL	608.15	EST
			150	150	HR	ALL PURPOSE EXCAVATOR RENTAL , TYPE I	608. 25	EST
			150	150	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
			300	300	HR	TRUCK RENTAL	608. 37	EST
			175	175	HR	LOADER RENTAL, TYPE I	608.40	EST
	300			300	CY	STONE FILL, TYPE I	613.10	33.3
			50	50	EA	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	EST
			50	50	EA	YIELDING MARKER POSTS	619.17	EST
			5000	5000	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	112
			3000	3000	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	247
			37.5	37.5	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-
			37.5	37.5	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
14627	SY	MAINLINE
3481	SY	SIDE ROADS
392	SY	ROUNDING
18500	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
15211	TON	MAINLINE (WEARING COURSE)
585	TON	SIDE ROADS (WEARING COURSE)
7606	TON	MAINLINE (LEVELING COURSE)
292	TON	SIDE ROADS (LEVELING COURSE)
306	TON	ROUNDING
24000	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: GUILDHALL-MAIDSTONE
PROJECT NUMBER: STP 2706 (I)

FILE NAME: ...07CI62\...07CI62.dgn
PROJECT LEADER: DOMEY
DESIGNED BY: PAVT MGMT
IPARM FILE NAME: 07CI62_05.i

PLOT DATE: 31-OCT-2011 10:43
DRAWN BY: PAVT MGMT
CHECKED BY: PAVT MGMT
SHEET 5 OF 18