

WEATHERSFIELD - ROUTE 106												
STP 2711 (1)												
STONE FILL & GEOTEXTILE SUMMARY SHEET												
ITEM 613.10 STONE FILL, TYPE I												
ITEM 613.11 STONE FILL, TYPE II												
ITEM 649.31 GEOTEXTILE UNDER STONE FILL												
DATE	INSPECTED AND FMED BY	START STATION	STOP STATION	POSITION	DESCRIPTION	STONE LENGTH (FT)	STONE WIDTH (FT)	STONE DEPTH (FT)	GEOTEXTILE WIDTH (FT)	ITEM 613.10 STONE FILL TYPE I (CY)	ITEM 613.11 STONE FILL TYPE II (CY)	ITEM 649.31 GEOTEXTILE (SY)
8/12/2009	RMT	204+38		LT	AREA #1 - SLOPE REPAIR ONLY (NO CULVERT)	18.0	12.5	1.75	12.50		14.58	28.0
		204+12	204+54	LT	AREA #1 - BENCH TO STABILIZE SHOULDER	24.0	7.5	1.75	7.50		11.67	20.0
8/13/2009	RMT	203+60		LT	AREA #2 - SLOPE REPAIR @ CULVERT OUTLET	22.0	15.0	1.75	15.00		21.39	38.7
		203+22	203+88	LT	AREA #2 - BENCH TO STABILIZE SHOULDER	53.0	7.5	1.75	7.50		28.76	44.2
	RMT	201+97		LT	AREA #3 - SLOPE REPAIR @ CULVERT OUTLET	18.0	15.0	1.75	15.00		17.50	30.0
	RMT	199+97		LT	AREA #4 - SLOPE REPAIR @ CULVERT OUTLET	20.0	15.0	1.75	15.00		19.44	33.3
8/14/2009	RMT	198+55		LT	AREA #5 - SLOPE REPAIR @ CULVERT OUTLET	48.0	12.5	2.34	12.50		52.00	88.7
		197+04	199+42	LT	AREA #5 - BENCH TO STABILIZE SHOULDER	190.0	7.5	2.34	7.50		123.80	188.3