STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS ITEM "A" 675.20	ITEM 675.50 "B" REMOVE SIGNS	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (In) lb/ft 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.0 lb/ft 2.42	SQUARE STEEL (In) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (In) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (In) 4.0 MOD. lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	TUBULAR STEEL Ø (In) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (In) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (In) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (In) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
123+55 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0	I					1		~~X~~ 10.6	LF																		VR-017		
123+55 RT	NO OUTLET	1	30	30	6.~~26~~ 25	I					1		~~X~~ 10.5	LF																		W14-2		
124+35 RT	MILL ST					I	1																								SALVAGED SIGN TO BE MOUNTED ON NEW POST.		
	STOP	1	30	30	6.~~26~~ 25	I					1		~~X~~ 10.0	LF																		R1-1		
130+10 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0	I					1		~~X~~ 10.0	LF																		VR-017		
130+70 RT	STOUGHTON POND RD.					I	1				1		~~X~~ 10.0	LF																		SALVAGED SIGN TO BE MOUNTED ON NEW POST.		
	STOP	1	30	30	6.~~26~~ 25	I																										R1-1		
		SF			~~SF~~ EA	EA.	SF				FT	FT ~~75~~ 51.1	FT			EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					
	SHEET TOTALS	28.~~78~~ 75			7	2						~~75~~																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEET AND THE VTRANS, SIGN POST DESIGN GUIDELINE.

TRAFFIC SIGN SUMMARY SHEET

PROJECT: **WEATHERSFIELD**
PROJECT NO.: **STP 2711(1)**
DATE: 8-06

DESIGN FILE NAME: p07c164.dgn
IPARM FILE NAME: p07c164_20.i
SURVEYED BY: LSW/JLR
SQUAD LEADER: ERD

PLOT DATE: 28-MAY-2010 13:49
SURVEY DATE: II 2008
DRAWN BY: JLR
SHEET: **20** OF **21**