



- NOTES:**
1. ALL CONCRETE SHALL BE ITEM 541.25 CONCRETE CLASS B.
 2. ALL REBAR SHALL BE #5 BARS AT 12" UNLESS OTHERWISE SPECIFIED AND SHALL BE PAID AS ITEM 507.15 REINFORCING STEEL.
 3. #5 DOWELS AT 12" SHALL BE DRILLED AND GROUTED INTO EXISTING WALLS (INCIDENTAL TO ITEM 507.15)
 4. THE CAST IRON GRATE WITH FRAME SHALL BE NEENAH OR EQUIVALENT, SHALL BE PLACED AT EXISTING GRADE TO FACILITATE DRAINAGE, AND SHALL BE PAID FOR AS ITEM 900.620, SPECIAL PROVISION (CAST IRON GRATE WITH FRAME, CONCAVE).
 5. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS FOR THE EXISTING STRUCTURE.

DROP INLET RETRO-FIT DETAIL

NOT TO SCALE

STA. 341+45 LT DROP INLET RETRO-FIT DETAIL SHEET

PROJECT NAME: GUILFORD-BRATTLEBORO	PLOT DATE: 29-JAN-2013 11:40
PROJECT NUMBER: STP 2707(1)	DRAWN BY: MWS
FILE NAME: /pave/07cl66/pcl66	CHECKED BY: JPB
DESIGNED BY: SRB	SHEET 8 OF 97
IPARM FILE NAME: 07C166_08	