STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #14

SHS = FHWA STANDARD HIGHWAY SIGNS BOOK

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
356+64 RT B 0+00 RT	Brattleboro | Guilford	1	72	10	5.00						2		X		X																	96	
	0050 1302 0000 / 0050 1307 0676	1 1	6 6	10 10	0.42 0.42																										VD-700 VD-700		E-138 E-138
BRATTLEBORO B 17+00 RT		1	30	30	6.25						1		X		X																WI-2R		SHS
B 19+00 RT	SCHOOL BUS STOP AHEAD	1	36	36	9.00						2		X		X																S3-1 ASTM TYPE IX FLUORESCENT YELLOW-GREEN SHEETING		SHS
	500 FEET	1	24	18	3.00																										WI6-2 ASTM TYPE IX FLUORESCENT YELLOW-GREEN SHEETING		SHS
B 19+00 LT	SPEED LIMIT 35	1	24	30	5.00						1		X		X																R2-1		SHS
B 20+29 RT	HIDDEN DRIVES	1	30	30	6.25						1		X		X																VW-060		E-154
B 22+10 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 22+10 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 22+90 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 22+90 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 23+70 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 23+70 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
B 24+50 LT		1	18	24	3.00						1		X		X																WI-8 ASTM TYPE IX FLUORESCENT YELLOW SHEETING		SHS
												FT 0	FT 210	FT		EA	LB	LB	LB		LB	LB	LB	LB									
SHEET TOTALS					SF 56.34	SF	EA. 0	EA.				FT 210					LB			EA.	LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #14

PROJECT NAME: GUILFORD-BRATTLEBORO
PROJECT NUMBER: STP 2707(1)

FILE NAME: /pave/07c166/pc166
PROJECT LEADER: PTS
DESIGNED BY: DAM
IPARM FILE NAME: 07C166_85

PLOT DATE: 29-JAN-2013 11:42
DRAWN BY: HJD
CHECKED BY: PTS
SHEET 85 OF 97