STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD HIGHWAY SIGNS BOOK	SIGN DETAIL DETAIL IN SHS	DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
WEST RUTLAND: 71+50.0, LT	HIDDEN DRIVES	1	30	30	6.25						1					~~X~~ 13' 6"		X														SIGN ID CODE VW-060			E-154
73+92.0, RT	0041 1128 0140	1	6	10	0.42						1				~~X~~ 5' 9"			X														SIGN ID CODE VD-700			E-138
77+88.0, RT	SPEED LIMIT 40	1	24	30	5.00						1					~~X~~ 13' 3"		X														SIGN ID CODE R2-1	X		
80+98.0, LT	SPEED LIMIT 40	1	24	30	5.00						1					~~X~~ 14' 6"		X														SIGN ID CODE R2-1	X		
84+48.0, ~~LT~~ RT	0041 1128 0160	1	6	10	0.42		•1				1				~~X~~ 7' 0"			X					•NEW MM RELOCATED A.O.B.E.									SIGN ID CODE VD-700			E-138
CASTLETON STATE HIGHWAY: 1+25.0, LT	ONLY ONLY						1				2					13' 0" ~~X~~ 13' 0"		X														SALVAGED SIGN TO BE RELOCATED ON NEW POSTS.	-	-	-
3+41.0, RT	REPORT EMERGENCY TO 1-800-265-2735 CROSSING #240-907C ON E HUBBARDTON RD	1	18	30	3.75																											NEW SIGN TO BE MOUNTED ON EXISTING CROSSING SIGNAL POLE. SIGN ID CODE 1-13a		74	
3+66.0, LT	REPORT EMERGENCY TO 1-800-265-2735 CROSSING #240-907C ON E HUBBARDTON RD	1	18	30	3.75																											NEW SIGN TO BE MOUNTED ON EXISTING CROSSING SIGNAL POLE. SIGN ID CODE 1-13a		74	
3+66.0, LT	REPORT EMERGENCY TO 1-800-265-2735 CROSSING #240-907C ON E HUBBARDTON RD	1	18	30	3.75																											NEW SIGN TO BE MOUNTED ON EXISTING SIGNAL CASE. SIGN ID CODE 1-13a		74	
												LF	LF	LF	LF ~~28~~ 12.75	LF ~~70~~ 67.25	LF		EA.	LB	LB	LB		LB	LB	LB	LB							
TOTALS					SF 28.34	SF	EA. ~~1~~ 2	SF				LF			LF ~~98~~ 80.00					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #15

PROJECT NAME: CASTLETON - WEST RUTLAND
PROJECT NUMBER: STP 2705(1)

FILE NAME: p07c168.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p07c168tss15.i

PLOT DATE: 04-JUN-2013 09:3
DRAWN BY: W.G.P.
CHECKED BY: D.E.G.
SHEET 71 OF 152