

GRAVEL DRIVE

STA 365+18.5  
 16'-10"  
 ITEM 621.20  
 W/ ANCHOR  
 (SEE NOTE 1)  
 STA 365+18.5  
 12'-6"  
 ITEM 621.71  
 STA 365+31.0

EXISTING BRIDGE RAIL TO REMAIN

STA 365+78.0  
 50'-0"  
 ITEM 621.70  
 STA 0+05.92  
 27'-0"  
 ITEM 621.20  
 W/6'-3"  
 SPACING  
 W/ANCHOR  
 STA 0+32.92

WESTBOUND

VT. ROUTE 4A

EASTBOUND

77'-0"  
 STA 365+85.0  
 ITEM 621.20  
 W/6'-3" SPACING  
 W/ANCHOR  
 STA 364+62.0  
 50'-0"  
 ITEM 621.70  
 STA 365+12.0  
 EXISTING BRIDGE RAIL TO REMAIN  
 STA 365+59.0  
 50'-0"  
 ITEM 621.70  
 STA 366+09.0  
 27'-0"  
 ITEM 621.20  
 W/6'-3" SPACING  
 W/ANCHOR  
 STA 0+13.92

BR 12 CASTLETON MM 6.921 = STA 365+42.88

NOTES:

1. THE CONTRACTOR SHALL INSTALL NEW 16' RADIUS PANEL WITH ANCHORS AT EACH END AS DIRECTED BY THE RESIDENT ENGINEER.
2. TOWN OF CASTLETON MM 6.936 (STA 366+22.08) = TOWN OF IRA MM 0.000 (STA 0+00.00)
3. REFERENCE THIS SHEET ALONG WITH SHEETS 79 & 80 FOR GUARDRAIL APPROACH SECTION DETAILS.

NOT TO SCALE

<b>BRIDGE DETAIL SHEET #4</b>	PROJECT NAME: CASTLETON - WEST RUTLAND
	PROJECT NUMBER: STP 2705(i)
	FILE NAME: p07cl68.dgn
	PLOT DATE: 04-JUN-2013 09:3
	PROJECT LEADER: D.E.G.
	DRAWN BY: W.G.P.
	DESIGNED BY: M.J.M.
	CHECKED BY: D.E.G.
	IPARM FILE: p07cl68bd4.i
	SHEET 84 OF 152