QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

	BRIDGE	TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				2300	2300	LF	REMOVAL OF EXISTING FENCE	620.55	20
				3250	3250	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	31.25
				75	75	LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED W/8 FEET POSTS	621.207	-
				250	250	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215	-
				36	36	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
				8518.75	8518.75	LF	REMOVE AND RESET GUARDRAIL	621.75	-
				9300	9300	LF	REMOVE AND RESET GUARDRAIL (DOUBLE-SIDED)	621.75	-
				903	903	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	-
				544	544	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	-
				2223	2223	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
				1500	1500	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
				6800	6800	HR	FLAGGERS	630.15	EST.
			1		1	LS	FIELD OFFICE, ENGINEERS	631.10	-
			1		1	LS	TESTING EQUIPMENT, CONCRETE	631.16	-
			1		1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3000		3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
		520			520	HR	EMPLOYEE TRAINEESHIP	634.10	-
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
				1	1	LS	TRAFFIC CONTROL	641.10	-
				2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
							BEGIN OPTION AA		
				79000	79000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	1758
				79000	79000	LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	1758
							END OPTION AA		
							BEGIN OPTION BB		
				53000	53000	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	908
				53000	53000	LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414	908
							END OPTION BB		
							BEGIN OPTION CC		
				110	110	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	7
				110	110	LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484	7
							END OPTION CC		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BOLTON-WATERBURY
PROJECT NUMBER: STP 2709(1)

FILE NAME: p07C172.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: p07C172_14.1

PLOT DATE: 4/17/2013
DRAWN BY: JBG/BMB
CHECKED BY: CDL
SHEET 14 OF 217