QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

	BRIDGE	TRAINING	FULL CE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
							BEGIN OPTION DD		
				38	38	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-
				38	38	EA	DURABLE LETTER OR SYMBOL, POLYUREA	646.494	-
							END OPTION DD		
				310000	310000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	1032
				211000	211000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	2632
				425	425	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	13
				160	160	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	8
				3400	3400	EA	LINE STRIPING TARGETS	646.76	167
				10780	10780	SY	GEOTEXTILE UNDER STONE FILL	649.31	113
				1310	1310	SY	GEOTEXTILE FOR SILT FENCE	649.51	15.5
				390	390	LB	SEED	651.15	EST
				1620	1620	LB	FERTILIZER	651.18	EST
				6	6	TON	AGRICULTURAL LIMESTONE	651.20	EST
				6	6	TON	HAY MULCH	651.25	EST
				380	380	CY	TOPSOIL	651.35	6
				2400	2400	SY	GRUBBING MATERIAL	651.40	34
				12450	12450	SY	TEMPORARY EROSION MATTING	653.20	138
				2480	2480	LF	BARRIER FENCE	653.50	25
				2480	2480	LF	EROSION LOG	653.60	25
				1	1	LS	TREE PROTECTION	656.85	-
				630	630	SF	TRAFFIC SIGNS, TYPE A	675.20	10.12
				1900	1900	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	1
				150	150	EA	REMOVING SIGNS	675.50	-
				36	36	EA	DELINEATOR WITH STEEL POST	676.10	-
				32	32	EA	REMOVAL OF EXISTING DELINEATOR	676.12	-
				285	285	EA	REMOVE AND REPLACE REFLECTOR UNIT	676.15	-
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
				27	27	EA	SPECIAL PROVISION (CORING CONCRETE)	900.620	-
				1	1	EA	SPECIAL PROVISION (CAP CURB DROP INLET)	900.620	-
				5800	5800	LF	SPECIAL PROVISION (REHABILITATE EXISTING FENCE)	900.640	74
				1	1	LS	SPECIAL PROVISION (CLEARING)	900.645	-
				135600	135600	SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT, PORTLAND CEMENT)	900.675	1420
				38400	38400	SY	SPECIAL PROVISION (COLD PLANING BITUMINOUS PAVEMENT)	900.675	385.6

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		GEOTEXTILE UNDER STONE FILL
2117	SY	ITEM DETAIL SUMMARY SHEET 2
8550	SY	DITCH CLEANING DETAIL SHEET
113	SY	ROUNDING
10780	SY	TOTAL
		TOPSOIL
180	CY	GUARDRAIL DETAIL SUMMARY SHEET 2
194	CY	ITEM DETAIL SUMMARY SHEET 2
6	CY	ROUNDING
380	CY	TOTAL
		TEMPORARY EROSION MATTING
900	SY	GUARDRAIL DETAIL SUMMARY SHEET 2
3624	SY	ITEM DETAIL SUMMARY SHEET 2
7788	SY	DITCH CLEANING DETAIL SHEET
138	SY	ROUNDING
12450	SY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BOLTON-WATERBURY
PROJECT NUMBER: STP 2709(1)

FILE NAME: x07C172.dgn
PROJECT LEADER: CDL
DESIGNED BY: BMB
PLOT FILE: x07C172_15.1

PLOT DATE: 04/17/2013
DRAWN BY: JBG/BMB
CHECKED BY: CDL
SHEET 15 OF 217