STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #1

SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	NEW SIGN POSTS: SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
THETFORD	2440 0911 XXXX	6	6	10	2.50						6	X			X															VD-700 SEE SHEET 76 FOR LOCATIONS		E-138
WEST FAIRLEE	2440 0916 XXXX	6	6	10	2.50						6	X			X															VD-700 SEE SHEET 76 FOR LOCATIONS		E-138
FAIRLEE	2440 0906 XXXX	13	6	10	5.42						13	X			X															VD-700 SEE SHEET 76 FOR LOCATIONS		E-138
THETFORD 2+12 LT							1 1				2		X		X															REPLACE DAMAGED POST		
	VERMONT VERMONT						1 1																										
							1 1																										
3+20 LT	Thetford Ctr. 4 / East Thetford 8	1 1	72 72	12 12	6.00 6.00						2		X		X																76	
	West Fairlee 2 / Chelsea 15	1 1	72 72	12 12	6.00 6.00																										76	
3+31 RT	BRIDGE 1 VT244	1	6	10	0.42						1	X			X															VD-701	75	
4+95 LT	BRIDGE 1 VT244	1	6	10	0.42						1	X			X															VD-701	75	
5+00 RT	SALT REDUCTION AREA	1	36	36	9.00						2		X		X															VW-290		E-150
	NEXT 6 MILES	1	24	18	3.00																									W7-3A		SHSM
7+42 LT	SPEED LIMIT 35	1	30	36	7.50						1		X		X															R2-1	74	SHSM
												FT 405	FT 105	FT		EA	LB	LB	LB		LB	LB	LB	LB								
		SHEET TOTALS	SF 54.76	SF	EA. 6	SF						FT 510					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: THETFORD-FAIRLEE
PROJECT NUMBER: STP 2710(1)

FILE NAME: $FILEABBREV$
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: 07C184_62

PLOT DATE: 14-OCT-2013 16:36
DRAWN BY: SNG
CHECKED BY: DAM
SHEET 61 OF 77