

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	TRAINING	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		EACH	REMOVING LARGE TREES	201.16				COLD PLANING, BITUMINOUS PAVEMENT
								0.2			0.2		ACRE	THINNING AND TRIMMING	201.30	EST.	18318	SY	MAINLINE
								225			225		CY	COMMON EXCAVATION	203.15	3	3289	SY	SIDE ROADS
								1600			1600		CY	EARTH BORROW	203.30	EST.	293	SY	ROUNDING
								1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	21900	SY	TOTAL
								21900			21900		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	293			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
								39400			39400		LF	MILLED RUMBLE STRIPS	213.10	415	15157	TON	MAINLINE (WEARING COURSE TYPE IVS)
								5280			5280		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	50	519	TON	SIDE ROADS (WEARING COURSE TYPE IVS)
								1940			1940		TON	AGGREGATE SHOULDERS, RAP	402.13	23	387	TON	PULL-OFFS (WEARING COURSE TYPE IVS)
								1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	5226	TON	LEVELING (TYPE IVS)
								24500			24500		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	231	3000	TON	SPOT LEVELING (TYPE IVS)
								1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	231	TON	ROUNDING
								1			1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-	24500	TON	TOTAL
								1			1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-			STONE FILL, TYPE I
								1			1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-	1188	CY	DITCH CLEANING
								19			19		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-	145	CY	SLOPE EROSION PREVENTION
								5			5		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-	7	CY	ROUNDING
								50			50		HR	POWER GRADER RENTAL	608.15	EST.			TOTAL
								300			300		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
								50			50		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
								600			600		HR	TRUCK RENTAL	608.37	EST.			
								40			40		HR	LOADER RENTAL, TYPE I	608.40	EST.			
								1340			1340		CY	STONE FILL, TYPE I	613.10	7			
								35			35		TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1			
								2			2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-			
								16			16		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1			
								12			12		SF	DETECTABLE WARNING SURFACE	618.30	-			
								160			160		EACH	YIELDING MARKER POSTS	619.17	EST.			
								3480			3480		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	10			
								10875			10875		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	12.5			
								50			50		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	-			
								64			64		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
								13525			13525		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	3.5			
								1200			1200		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
								6800			6800		HR	FLAGGERS	630.15	EST.			
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
								520			520		HR	EMPLOYEE TRAINEESHIP	634.10	-			

PROJECT NAME: SWANTON-SHELDON  
 PROJECT NUMBER: STP 2715(I)  
 FILE NAME: ...\\Plot+ Files\p07c186qs0l.dgn PLOT DATE: 4/24/2014  
 PROJECT LEADER: JLL DRAWN BY: STANTEC  
 DESIGNED BY: MCF CHECKED BY: JLL  
 SHEET 5 OF 121

