


# Pedestrian Signals (16")

Captive wing nut style door latch assemblies

Vandal tabs on each side to prevent unauthorized access


Three hinge fins for greater strength



All external hardware is stainless steel

### Features:

- **Invertable design:** Door is attached using stainless steel ball pins for easy door removal and may swing from either end of the body (for left or right of door mounting).
- **One style universal maintenance housing** will fit any mounting application!
- Lens and Gasket mounted to door with four stainless steel tabs and screws using threaded brass inserts in door -- **NOT glued to the door!**
- Rotatable sockets (for proper lamp orientation) are standard
- **Multiple Body options:** Die cast aluminum, Polycarbonate
- **Multiple Door options:**
  - Black Polycarbonate w/integral "Z" style protectors
  - Black Polycarbonate, open style
  - Black Die cast aluminum, open style



## Options:

## Traffic Parts, Inc.

### 1. Body Configuration

- N=Body not drilled
- C=Drilled for clamdoor mounting
- P=Drilled for top/bottom pipe mount
- B=Drilled for both with plugs  
(Universal maintenance housing)

### 2. Message Configuration

- N=Body + Door only  
(No lens, gasket, reflector, sockets)

Conf	Hand	Man
1	Incand*	Incand*
2	LED**	Incand*
3	LED**	LED**
A	LED Side by Side (Hand/Man)	
E	LED Overlap H/M, Cntdown	
F	LED Overlap, H/M, Cntdown, I-Look	

\*Lamps not included (use 60,67,69w)

\*\*LED=Socket mount LED module

### 3. Lens Type

- N=None (LED ready) G=Glass

### 4. Body/Hardware Color/Mat

- Aluminum Body Options:  
Y=Yellow B=Gloss Blk F=Flat Blk  
G=Dk Grn L=Light Grn Z=Bronze  
A=Aluminum X=Special
- Polycarbonate Body Options:  
P=Yellow Q=Black R=Dk Green

### 5. Terminal Block Type

- 2=5 position, 20a
- 3=5 position, 30a
- N=None


### 6. Mounting Hardware

- N=None
- 2=Clamdoor 2 Mount (3 pos block)
- 3=Clamdoor 3 Mount (10 pos block)


### 7. Visor/Door (All Black)

All visors are 6" AL tunnel, black

Door	w/o Visor	w/ Visor
Z-crate, PC	N	T
Open, PC	P	X
Open, AL	Q	Y



Clamdoor 2 Mounting



Clamdoor 3 Mounting

SSPED	-	P	N	N	-	Q	2	N	-	Q	-	-	-	-	-	-	-	-	-			
Option Category	➔	1	2	3		4	5	6		7	8	9	10	11	12	13	14	15	16	17	18	19