

ITEM DETAIL SUMMARY SHEET 1

LOCATION			GUARDRAIL			MISCELLANEOUS													REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.60	621.80	203.15	203.16	203.30	301.26	402.13	604.40	604.412	604.415	604.42	613.10	616.21	616.28	616.40		616.41
			S.B. G.R. GALV. LF	ANCHOR FOR S.B. RAIL EACH	REMOVAL & DISPOSAL OF GUARDRAIL LF	COMMON EXCAVATION CY	SOLID ROCK EXCAVATION CY	EARTH BORROW CY	SUBBASE OF CRUSHED GRAV., FINE GRADED CY	AGGREGATE SHOULDERS, RAP TON	CHAN ELEV. OF DI, CB OR MH EACH	REHAB DI, CB, OR MH, CLASS I EACH	REHAB DI, CB, OR MH, CLASS II EACH	CHAN ELEV. OF SEWER MH EACH	STONE FILL, TYPE I CY	VERTICAL GRANITE CURB LF	C-I-P CONC. CURB, TYPE B LF	REMOVING & RESETTING CURB LF		REMOVAL OF EXISTING CURB LF
US ROUTE 5																				
VILLAGE OF BARTON																				
257+13.60	315+90.24	LT&RT								107			33	8	17					
262+20	262+28	RT													2.1					
270+20	270+29	RT													2.3					
284+73		RT				4.5			2.5							27.0		27.0		
284+87		LT				1.7			0.9							14.0		14.0		
291+97		LT				2.2			1.2							19.0		19.0		
292+33		LT				0.6			0.4							9.0		9.0		
297+82		LT				3.4			1.9							20.0		20.0		
297+82		RT				1.1			0.6											
298+51		RT				2.0			1.1							11.0		11.0		
298+88		RT				1.6			0.9							9.0				
301+58		RT				0.4			0.2											
303+92		LT				2.6			1.4							14.0		14.0		
304+24		LT				3.2			1.8							26.0		26.0		
305+45		RT				2.0			1.1							14.0		14.0		
306+20		RT				2.4			1.3							14.0		14.0		
306+45		RT				1.8			1.0							10.5		10.5		
306+96		RT				2.8			1.5							16.5		16.5		
309+75	310+89	LT																		
311+58.0	320+08.0	LT	814.5	2	842			50												
VT ROUTE 16																				
VILLAGE OF BARTON																				
92+18.88	124+44.96	LT&RT								62			12	3	9					
92+48.0	93+39.0	LT	102	1	91			25												
115+06	115+12	RT																		
115+14		LT				0.7			0.4							5.0		5.0		
115+14		RT				0.8			0.5											
116+54		LT				0.7			0.4							5.0		5.0		
116+54		RT				0.9			0.5							5.0		5.0		
117+93		RT				0.6			0.3							5.0		5.0		
118+19		RT				0.6			0.4							7.8		7.8		
SHEET 7 SUBTOTALS:			916.5	3	933	36.6		75	20.3	169		45	11	26	4.4	231.8		222.8		

ITEM DETAIL SUMMARY SHEET #1	PROJECT NAME: BARTON	
	PROJECT NUMBER: STP 2702(1)	
	FILE NAME: p07c192.dgn	PLOT DATE: 30-OCT-2013 17:0
	DESIGNED BY: STANTEC	DRAWN BY: STANTEC
IPARM FILE: p07c192idss01.i		CHECKED BY: STANTC
		SHEET 7 OF 75