ITEM DETAIL SUMMARY SHEET 2

LOCATION			MISCELLANEOUS																			REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	616.47 BIT. CONC. GUTTERS & TRAFF. ISL. TON	618.10 PORTLAND CEMENT CONC., 5 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	619.17 YIELDING MARKER POSTS EACH	629.20 ADJUST ELEV VALVE BOX EACH	649.31 GEOTEXTILE UNDER STONE FILL SY	651.40 GRUBBING MATERIAL SY	653.20 TEMPORARY EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EACH											
US ROUTE 5																						
VILLAGE OF BARTON																						
257+13.60	315+90.24	LT&RT				8	18															QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE SHEET 12.
262+20	262+28	RT						9	6	6												REPAIR SLOPE EROSION - SEE DETAIL ON SHEET 13
270+20	270+29	RT						10	7	7												REPAIR SLOPE EROSION - SEE DETAIL ON SHEET 13
284+73		RT		14.8	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 6
284+87		LT		5.4	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
291+97		LT		7.2	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
292+33		LT		2.1	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
297+82		LT		11.2	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 6
297+82		RT		3.7	10.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
298+51		RT		6.7	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
298+88		RT		5.1	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
301+58		RT		1.4	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
303+92		LT		8.7	16.0																	CONSTRUCT SIDEWALK RAMP, TYPE 6
304+24		LT		10.6	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
305+45		RT		6.6	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
306+20		RT		7.9	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
306+45		RT		5.8	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
306+96		RT		9.1	8.0																	CONSTRUCT SIDEWALK RAMP, TYPE 1
309+75	310+89	LT	10.4																			CONSTRUCT BITUMINOUS CONCRETE GUTTER, SEE DETAIL ON SHEET 13.
311+58.0	320+08.0	LT								50	2											INSTALL ANCHOR @ STA. 311+58.0 AND 320+08.0, LT.
VT ROUTE 16																						
VILLAGE OF BARTON																						
92+18.88	124+44.96	LT&RT				11	6															QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE SHEET 12.
92+48.0	93+39.0	LT								25	1											CONNECT TO EXISTING GUARDRAIL AT FIRST BRIDGE POST @ STA. 92+48.0 INSTALL ANCHOR @ STA. 93+39.0
115+06	115+12	RT	1.2																			CONSTRUCT BITUMINOUS CONCRETE GUTTER, SEE DETAIL ON SHEET 13.
115+14		LT		2.2	10.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
115+14		RT		2.8	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
116+54		LT		2.2	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
116+54		RT		2.9	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
117+93		RT		2.0	8.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
118+19		RT		2.1	6.0																	CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
SHEET 8 SUBTOTALS:			11.6	120.5	178	19	24	19	13	88	3											

ITEM DETAIL SUMMARY SHEET #2

PROJECT NAME: BARTON
PROJECT NUMBER: STP 2702(I)

FILE NAME: p07c192.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07c192idss02.i

PLOT DATE: 30-OCT-2013 17:0
DRAWN BY: STANTEC
CHECKED BY: STANTC
SHEET 8 OF 75