

ITEM DETAIL SUMMARY SHEET 3

LOCATION			GUARDRAIL			MISCELLANEOUS													REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.60	621.80	203.15	203.16	203.30	301.26	402.13	604.40	604.412	604.415	604.42	613.10	616.21	616.28	616.40		616.41
			S.B. G.R. GALV. LF	ANCHOR FOR S.B. RAIL EACH	REMOVAL & DISPOSAL OF GUARDRAIL LF	COMMON EXCAVATION CY	SOLID ROCK EXCAVATION CY	EARTH BORROW CY	SUBBASE OF CRUSHED GRAV., FINE GRADED CY	AGGREGATE SHOULDERS, RAP TON	CHAN ELEV OF DI, CB OR MH EACH	REHAB DI, CB, OR MH, CLASS I EACH	REHAB DI, CB, OR MH, CLASS II EACH	CHAN ELEV. OF SEWER MH EACH	STONE FILL, TYPE I CY	VERTICAL GRANITE CURB LF	C-I-P CONC. CURB, TYPE B LF	REMOVING & RESETTING CURB LF		REMOVAL OF EXISTING CURB LF
VT ROUTE 16 (CONT.) VILLAGE OF BARTON																				
	119+70	LT				0.7			0.4								5.0		5.0	
	120+04	RT				1.2			0.6								12.0		12.0	
	122+67	LT				1.7			0.9											
	122+75	RT				0.5			0.3											
VT ROUTE 58 VILLAGE OF ORLEANS																				
	8+07.84	39+75.84	LT&RT							61	4	21	5	8						
	8+69.0	9+00.0	RT	52	1	12.5		25												
	12+87	LT				2.5			1.4								14.0			
	13+91	LT				2.9			1.6								20.0			
	14+77	LT				1.4			0.8								12.5			
	15+07	LT				1.7			0.9								12.0			
	16+56.12	17+02.41	LT&RT					118												
	16+84	LT				2.0			1.1								7.0			
	17+30.0	17+60.0	LT	50		28														
	17+42	LT				2.2			1.2						16.0			16.0		
	17+74	LT				3.4			1.8						20.0			20.0		
	18+09	RT				5.6			3.0						23.0			15.0		
	18+12	LT				2.3			1.3						4.0					
	19+66	LT				1.4			0.7											
	20+52	LT				10.7			5.8						37.5			20.0		
	25+17	LT				3.3			1.8						12.0			13.0		
	25+79.0	32+47.0	LT	712	2	665		50						2.1						
	34+70	LT																		
	35+52	35+98	RT																	
SHEET 9 SUBTOTALS:			814	3	705.5	43.5	118	75	23.6	61	4	21	5	8	2.1	112.5	17.0	65.5	101	
SHEET 7 SUBTOTALS:			916.5	3	933	36.6	-	75	20.3	169		45	11	26	4.4	-	231.8	-	222.8	
PROJECT SUBTOTALS:			1730.5	6	1638.5	80.1	118	150	43.9	230	4	66	16	34	6.5	112.5	248.8	65.5	323.8	
ROUNDING:			19.5	-	11.5	4.9	2	-	6.1	5	-	-	-	-	0.5	7.5	6.2	4.5	6.2	
TOTALS:			1750	6	1650	85	120	150	50	235	4	66	16	34	7	120	255	70	330	

**ITEM
DETAIL
SUMMARY
SHEET #3**

PROJECT NAME: BARTON	
PROJECT NUMBER: STP 2702(1)	
FILE NAME: p07c192.dgn	PLOT DATE: 30-OCT-2013 17:0
PROJECT LEADER: JLL	DRAWN BY: STANTEC
DESIGNED BY: STANTEC	CHECKED BY: STANTC
IPARM FILE: p07c192idss03.i	SHEET 9 OF 75