

COMPOSITE QUANTITY SHEET 3

TROY STP HES 2718 (1)					TROY STP 2717 (1)			NORTH TROY STP 2620 (1)				TROY STP 2621 (1)				TOTALS		DESCRIPTIONS			
ROADWAY	EMPLOYEE TRAINEESHIP	EROSION CONTROL	FULL C. E.	HES	ROADWAY	EROSION CONTROL	FULL C. E.	ROADWAY	BRIDGE	EROSION CONTROL	FULL C. E.	ROADWAY	BRIDGE	EROSION CONTROL	FULL C. E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
37500					19800			9400				8000				74700		LF	DURABLE 4 INCH YELLOW LINE , THERMOPLASTIC	646.412	-
230					60			100								390		LF	DURABLE 24 INCH STOP BAR , THERMOPLASTIC	646.482	-
45					17			35				18				115		EACH	DURABLE LETTER OR SYMBOL , THERMOPLASTIC	646.492	-
								380								380		LF	DURABLE CROSSWALK MARKING , THERMOPLASTIC	646.502	-
45000					48000			19100				15800				127900		LF	TEMPORARY 4 INCH WHITE LINE , PAINT	646.602	-
37500					39500			18800				16000				111800		LF	TEMPORARY 4 INCH YELLOW LINE , PAINT	646.612	-
230					115			200								545		LF	TEMPORARY 24 INCH STOP BAR , PAINT	646.682	-
45					34			70				36				185		EACH	TEMPORARY LETTER OR SYMBOL , PAINT	646.692	-
								760								760		LF	TEMPORARY CROSSWALK MARKING , PAINT	646.702	-
1800					920			500				300				3520		EACH	LINE STRIPING TARGETS	646.76	-
		5600				4950				710				1300		12560		SY	GEOTEXTILE UNDER STONE FILL	649.31	-
30					30			30				30				120		LB	SEED	651.15	-
250					250			250				250				1000		LB	FERTILIZER	651.18	-
1					1			1				1				4		TON	AGRICULTURAL LIMESTONE	651.20	-
25					25			25				25				100		CY	TOPSOIL	651.35	-
		7900				3800				1850				3200		16750		SY	TEMPORARY EROSION MATTING	653.20	-
111				179				213				15				518		SF	TRAFFIC SIGNS , TYPE A	675.20	-
265				535				395				30				1225		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	-
33				62	1			37				4				137		EACH	REMOVING SIGNS	675.50	-
				11												11		EACH	ERECTING SALVAGED SIGNS	675.60	-
26					4							1				31		EACH	DELINEATOR WITH STEEL POST	676.10	-
9												1				10		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-
1					1			1				1				4		LU	PRICE ADJUSTMENT , FUEL (N. A. B. I.)	690.50	-
					35600											35600		SY	SPECIAL PROVISION (COLD MIXED RECYCLED BITUMINOUS PAVEMENT , PORTLAND CEMENT)	900.675	-
1200					450			970				130				2750		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL , DRIVES)	900.675	-
					35600											35600		SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE , PORTLAND CEMENT)	900.675	-
					560											560		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	-
					160											160		TON	SPECIAL PROVISION (PORTLAND CEMENT FOR COLD MIX RECYCLING)	900.680	-
2																2		EACH	ANCHOR FOR STEEL BEAM RAIL (COD*OI DATED 9-21-09)	621.60	-

PROJECT NAME: NORTH TROY / TROY
PROJECT NUMBER: STP HES 2718(1) / STP 2717(1)
STP 2620(1) / STP 2621(1)
FILE NAME: p07c200.dgn PLOT DATE: 25-OCT-2011 13:59
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: JLL
IPARM FILE: p07c200cqs03.i SHEET 5 OF 116