

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES				TOTALS		DESCRIPTORS		
ROADWAY	EROSION CONTROL	FULL C. E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
100			100		CY	EARTH BORROW	203.30	-
1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
950			950		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	17
3930			3930		TON	SUBBASE, RAP	301.40	4
1150			1150		TON	AGGREGATE SHOULDERS	402.12	13
1245			1245		TON	AGGREGATE SHOULDERS, RAP	402.13	4
4			4		CWT	EMULSIFIED ASPHALT	404.65	0.1
1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.
5870			5870		CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	4
						BEGIN OPTION AA		
4200			4200		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% RAP CONTENT)	490.30	168
4200			4200		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% < RAP CONTENT < 15.0%)	490.30	168
4200			4200		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30	168
4200			4200		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30	168
						END OPTION AA		
1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	EST.
1			1		LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	EST.
1			1		LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.) (NON-LIMITED ACCESS HIGHWAY)	490.33	EST.
1			1		LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	EST.
60			60		HR	POWER GRADER RENTAL	608.15	EST.
60			60		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
40			40		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
60			60		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
60			60		HR	TRUCK RENTAL	608.37	EST.
60			60		HR	LOADER RENTAL, TYPE I	608.40	EST.
2			2		MGAL	DUST CONTROL WITH WATER	609.10	0.4
	1460		1460		CY	STONE FILL, TYPE I	613.10	5
1			1		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
22			22		EACH	YIELDING MARKER POSTS	619.17	-
62.5			62.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
25			25		LF	STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.206	-
75			75		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	-
4			4		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-
252			252		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
880			880		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
2640			2640		HR	FLAGGERS	630.15	EST.
		0.25	0.25		LS	FIELD OFFICE, ENGINEERS	631.10	EST.

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
933	SY	MAINLINE
17	SY	ROUNDING
950	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
3015	TON	MAINLINE WEARING COURSE (TYPE IVS)
8	TON	SIDE ROAD WEARING COURSE (TYPE IVS)
1009	TON	LEVELING (TYPE IVS)
168	TON	ROUNDING
4200	TON	TOTAL
		TEMPORARY EROSION MATTING
1253	SY	DITCH CLEANING
100	SY	M.T.S. FLARED CONSTRUCTION
2420	SY	SEED PROTECTION
27	SY	ROUNDING
3800	SY	TOTAL

PROJECT NAME: TROY	PLOT DATE: 25-OCT-2011 14:01
PROJECT NUMBER: STP 2717(1)	DRAWN BY: STANTEC
FILE NAME: p07b198.dgn	CHECKED BY: JLL
PROJECT LEADER: JLL	DESIGNED BY: MCF
IPARM FILE: p07b198qs01.i	SHEET 51 OF 116