ITEM DETAIL SUMMARY SHEET

LOCATION			GUARDRAIL					MISCELLANEOUS												REMARKS
BEGIN STATION	END STATION	POS.	621.20 S.B. GR. GALV.	621.206 S.B. GR. GALV./ NEST.	621.216 HD S.B. GR. GALV./ NEST.	621.50 MTS, FLARED	621.80 REMOVAL & DISPOSAL OF GUARDRAIL	203.30 EARTH BORROW	301.40 SUBBASE, RAP	653.20 TEMPORARY EROSION MATTING	676.10 DELINEATOR WITH STEEL POST									
			LF	LF	LF	EA	LF	CY	TON	SY	EACH									
VT ROUTE 105																				
TROY:																				
23+23.2	126+19.2	LT&RT							3926											CORRECT SUPERELEVATION AND GRADATION DEFICIENCIES AS DIRECTED BY THE RESIDENT ENGINEER.
26+30.5	27+93	RT	62.5	25		2	162	50		50	2									INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 26+30.5 AND 27+55.5, RT
																				INSTALL GUARDRAIL AT BR#53 PER THE GUARDRAIL DETAIL SHEET.
26+73.5	28+23.5	LT			75	2	90	50		50	2									INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED AT STA. 26+73.5 AND 28+23.5, LT
																				INSTALL GUARDRAIL AT BR#53 PER THE GUARDRAIL DETAIL SHEET.
SHEET SUBTOTALS:			62.5	25	75	4	252	100	3926	100	4									
ROUNDINGS:			-	-	-	-	-	-	4	-	-									
TOTALS:			62.5	25	75	4	252	100	3930	100	4									

THIS SHEET NOT USED FOR RECORD PLANS. SEE LAYOUT SHEETS FOR DETAILS.

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: TROY
PROJECT NUMBER: STP 2717(1)

FILE NAME: p07b198.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07b198idss.i

PLOT DATE: 25-OCT-2011 14:01
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 53 OF 116