ITEM DETAIL SUMMARY SHEET

LOCATION			GUARDRAIL					MISCELLANEOUS										REMARKS
BEGIN STATION	END STATION	POS.	621.20 S.B. GR. GALV.	621.50 MTS, FLARED	621.76 REPLACE GUARDRAIL POST ASSEBLY	621.77 REPLACE GUARDRAIL BEAM UNIT	621.80 REMOVAL & DISPOSAL OF GUARDRAIL	203.30 EARTH BORROW	203.40 SHOULDER BERM REMOVAL	604.40 CHAN ELEV OF DI, CB OR MH	604.412 REHAB DI, CB, OR MH, CLASS I	653.20 TEMPORARY EROSION MATTING	676.10 DELINEATOR WITH STEEL POST	676.12 REMOVAL OF EXISTING DELINEATOR				
			LF	EA	EA	EA	LF	CY	LF	EA	EA	SY	EA	EA				
VT ROUTE 243																		
TROY:																		
6+12	45+78	LT&RT			80	40			2420	1	1							QUANTITIES FOR USE AS DIRECTED BY THE RESIDENT ENGINEER
36+95	37+45	LT	12.5	1			50	25				25	1	1				INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA. 37+07.5 TO STA. 37+45.0, LT
SHEET SUBTOTALS:			12.5	1	80	40	50	25	2420	1	1	25	1	1				
ROUNDINGS:			-	-	-	-	-	-	30	-	-	-	-	-				
TOTALS:			12.5	1	80	40	50	25	2450	1	1	25	1	1				

THIS SHEET NOT USED FOR RECORD PLANS. SEE LAYOUT SHEETS FOR DETAILS

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: TROY
PROJECT NUMBER: STP 2621(1)

FILE NAME:
PROJECT LEADER: JLL
DESIGNED BY: MCF
IPARM FILE: p06c210idss.i

PLOT DATE: 25-OCT-2011 14:04
DRAWN BY: STANTEC
CHECKED BY: JLL
SHEET 105 OF 116