LOCATION			DROP INLETS			CURB & SIDEWALK			GUARDRAIL										MISCELLANEOUS				REMARKS
			604.412	604.415	604.418	616.21	618.10	618.30	621.20	621.205	621.60	621.737	621.75	621.76	621.77	621.79	621.80	676.10	613.10	649.31	651.15	653.20	
MM	MM	POS	REHAB. DI, CB, OR MH, CLASS I	REHAB. DI, CB, OR MH, CLASS II	REHAB. DI, CB, OR MH, CLASS III	VERTICAL GRANITE CURB	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	DETECT. WARNING SURFACE (DWS)	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	ANCHOR FOR STEEL BEAM RAIL	GUARDRAIL APPROACH SECTION, GALV. HD STEEL BEAM	REMOVE AND RESET GUARDRAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	ADJUST HEIGHT OF GUARDRAIL	REMOVAL & DISPOSAL OF GUARDRAIL	DELIN. W/STEEL POST	STONE FILL, TYPE I	GEOT. UNDER STONE FILL	SEED	TEMPORARY EROSION MATTING	
			EACH	EACH	EACH	LF	SY	SF	LF	LF	EACH	EACH	LF	EACH	EACH	LF	LF	EACH	CY	SY	LB	SY	
	CANAAN																						
	VT ROUTE 114																						
409+25	440+30	LT/RT	10	1	1																		ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
409+26	440+31	LT/RT																			13	707	SEE DITCH CLEANING DETAIL SHEETS
409+27	440+32	LT/RT																			2	100	ESTIMATED QUANTITY TO BE USED AT GUARDRAIL TERMINALS
BRIDGE 52																							
409+31	410+43.5	RT															112.5						
409+31	410+18.5	RT							89.5		1							1					SEE STANDARD G-1d
410+18.5	410+43.5	RT										1											
410+43.5	411+56	RT																					RETAIN STEEL BEAM BRIDGE RAIL
411+56	412+46	RT															90.0						
411+56	411+81	RT										1											
411+81	412+43.5	RT							64.5		1							1					SEE STANDARD G-1d
BRIDGE 52																							
409+58	410+43.5	LT															85.5						
409+56	410+18.5	LT							64.5		1							1					SEE STANDARD G-1d
410+18.5	410+43.5	LT										1											
410+43.5	411+56	LT																					RETAIN STEEL BEAM BRIDGE RAIL
411+56	412+66	LT															110.0						
411+56	411+81	LT										1											
411+81	412+68.5	LT							89.5		1							1					SEE STANDARD G-1d
430+20	430+23	RT					2.8	8.0															CONSTRUCT SIDEWALK LANDING W/DWS @ 430+21
432+91	432+96	RT					2.2	8.0															CONSTRUCT SIDEWALK LANDING W/DWS @ 432+95
	CANAAN																						
	VT ROUTE 253																						
C0+08	C113+68	LT/RT	7	1	1																108		ESTIMATED QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER
C0+08	C113+68	LT/RT																			60	3595	SEE DITCH CLEANING DETAIL SHEETS
C0+08	C113+68	LT/RT																			2	150	ESTIMATED QUANTITY TO BE USED AT GUARDRAIL TERMINALS
C23+18	C30+77	RT															759.0						
C23+14.5	C30+77	RT							766.5		2							2					SEE STANDARD G-1d
C33+66	C48+78	RT															1512.0						
C33+66	C37+66.0	RT							402.0		1							1					SEE STANDARD G-1d
C37+66	C47+78.5	RT								1012.5													
C47+78.5	C48+78.5	RT							102.0		1							1					SEE STANDARD G-1d
C40+60	C42+25	RT																	19				SEE SHOULDER STABILIZATION DETAIL ON SHEET 9
C51+73	C52+10.5	RT							39.5		1						37.5	1					SEE STANDARD G-1d
C52+10.5	C90+35.5	RT											3825.0										
C90+35.5	C90+73	RT							39.5		1						37.5	1					SEE STANDARD G-1d
C53+60	C55+85	RT																	26				SEE SHOULDER STABILIZATION DETAIL ON SHEET 9
C66+00	C68+40	RT																	28				SEE SHOULDER STABILIZATION DETAIL ON SHEET 9
C79+75	C82+10	RT																	27				SEE SHOULDER STABILIZATION DETAIL ON SHEET 9
C86+90	C88+10	RT																	14				SEE SHOULDER STABILIZATION DETAIL ON SHEET 9
C91+86	C91+91	LT					2.2	8.0															CONSTRUCT SIDEWALK LANDING W/DWS @ C91+86
C93+96	C94+01	RT					1.9	8.0															CONSTRUCT SIDEWALK LANDING W/DWS @ C94+48
	SUBTOTAL SHEET 14		1	0	0	0.0	0.0	0	1123.5	0.0	18	0	837.5	135	70	500.0	1083.0	68	335	1507	642	16850	
	SUBTOTAL SHEET 15		0	0	0	31.5	8.4	8.0	2809.5	850.0	17	4	437.5	0	0	0.0	3539.0	17	0	0	3	203	
	SUBTOTAL SHEET 16		17	2	2	0.0	9.1	32.0	1657.5	1012.5	10	4	3825.0	0	0	0.0	2744.0	10	114	0	185	4552	
	PROJECT SUBTOTAL		18	2	2	31.5	17.5	40.0	5590.5	1862.5	45	8	5100.0	135	70	500.0	7366.0	95	449	1507	830	21605	
	TOTAL ROUNDING		0	0	0	0.5	2.5	0.0	34.5	37.5	0	0	50.0	0	0	0.0	34.0	0	11	13	0	95	
	PROJECT TOTAL		18	2	2	32.0	20.0	40.0	5625.0	1900.0	45	8	5150.0	135	70	500.0	7400.0	95	460	1520	830	21700	

CLD 14-0197

PROJECT NAME: LEMINGTON-CANAAN
PROJECT NUMBER: STP 2723(I)

FILE NAME: z07c214frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
ITEM DETAIL SHEET 3

PLOT DATE: 2/28/2015
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 16 OF 162