

LOCATION				FEET OF DITCHING PERCENT GRADE		613.10	613.11	649.31	651.15	653.20	REMARKS
SITE	STA	STA	POS	0-2.5	2.5-10	STONE FILL, TYPE I	STONE FILL, TYPE II	GEOT. UNDER STONE FILL	SEED	TEMP EROS. MATT.	
				(CY)	(CY)	(SY)	(LBS)	(SY)			
LEMINGTON VT 102											
1	L193+80	L199+00	RT	520					4	231	
2	L193+80	L214+35	LT	2055					15	913	
3	L235+50	L245+00	LT	950					7	422	
4	L239+50	L245+00	RT	550					4	244	
5	L268+75	L308+90	LT	4015					28	1784	
6	L301+50	L306+20	RT	470					3	209	
7	L330+40	L331+65	LT	125					1	56	
8	L334+55	L365+00	LT	3045					22	1353	
LEMINGTON VT 102 SUBTOTAL				11730	0	0		0	84	5212	
CANAAN VT 102											
9	64+40	71+45	LT	705					5	313	
10	64+40	71+60	RT	720					5	320	
11	86+30	87+90	LT		160	24		107			
12	86+30	87+75	RT		145	21		97			
13	91+00	96+10	LT	510					4	227	
14	97+70	107+70	LT	1000					7	444	
15	110+90	117+25	LT	635					5	282	
16	121+70	144+65	LT	2295					17	1020	
17	144+65	159+20	RT	1455					11	647	
18	156+20	173+30	LT	1710					13	760	
19	173+35	177+95	RT	460					3	204	
20	191+40	213+75	LT	2235					16	993	
21	210+15	211+30	RT		115	17		77			
22	213+85	216+90	RT		305	45		203			
23	216+25	275+00	LT	5875					43	2611	
24	254+50	259+25	RT	475					3	211	
25	277+20	287+65	RT	1045					8	464	
26	279+00	293+65	LT	1465					11	651	

LOCATION				FEET OF DITCHING PERCENT GRADE		613.10	613.11	649.31	651.15	653.20	REMARKS
SITE	STA	STA	POS	0-2.5	2.5-10	STONE FILL, TYPE I	STONE FILL, TYPE II	GEOT. UNDER STONE FILL	SEED	TEMP EROS. MATT.	
				(CY)	(CY)	(SY)	(LBS)	(SY)			
27	295+40	305+45	RT		1005	149		670			
28	298+30	303+60	LT	530					4	236	
29	305+60	323+40	LT	1780					13	791	
30	316+80	323+15	RT	635					5	282	
31	323+40	328+70	LT		530	79		353			
32	328+70	335+60	LT	690					5	307	
CANAAN VT 102 SUBTOTAL				24220	2260	335		1507	178	10763	
CANAAN VT 114											
33	411+60	427+50	RT	1590					12	707	
CANAAN VT 114 SUBTOTAL				1590	0	0		0	12	707	
CANAAN VT 253											
34	C4+90	C10+00	RT	510					4	227	
35	C16+15	C33+70	LT	1755					13	780	
36	C36+70	C45+95	LT	925					7	411	
37	C49+10	C90+80	LT	4170					31	1853	
38	C101+45	C108+75	LT	730					5	324	
CANAAN VT 253 SUBTOTAL				8090	0	0		0	60	3595	
											SEE ITEM DETAIL SHEET FOR ROUNDING AND PROJECT TOTAL

PROJECT NAME: LEMINGTON-CANAAN
PROJECT NUMBER: STP 2723(I)
FILE NAME: z07c2i4frm.dgn PLOT DATE: 2/28/2015
PROJECT LEADER: P. SHEDD DRAWN BY: W. GORDON
DESIGNED BY: N. LEMAY CHECKED BY: P. SHEDD
DITCH CLEANING DETAIL SHEET 1 SHEET 22 OF 162

CLD 14-0197