STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #11

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL		
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	SQUARE STEEL (In)					TUBULAR ALUMINUM Ø (In)				TUBULAR STEEL Ø (In)					W-SHAPE STEEL				SIGNS REQUIRED		SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0 MOD	FOUNDATION	3.0	3.5	4.0	5.0	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE					
												lb/ft					lb/ft				lb/ft												
												1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
340+06 RT	Treatment Plant Rd	1	72	12	6.00						2		X		X															D3-1		158	
343+25 LT		1	30	30	6.25						1		X		X															W11-6H FOLDING/HINGED SEE STANDARD E-153 FOR HINGE DETAIL			E-153
348+10 RT	END JCT JCT	1 1 1	24 21 21	12 15 15	2.00 2.19 2.19						2									2	140.6								#3D	GREEN ON WHITE GREEN ON WHITE GREEN ON WHITE	M4-6 M2-1 M2-1		
	VERMONT 102 VERMONT 114 VERMONT 253	1 1 1	30 30 30	24 24 24	5.00 5.00 5.00																									MI-5 MI-5 MI-5			E-136B E-136B E-136B
350+59 RT	SCHOOL	1	36	12	3.00				1																					FLUORESCENT YELLOW GREEN INSTALL BELOW RETAINED SCHOOL SIGN	S4-3P		
352+55 RT		1	36	36	9.00						2		X		X															W3-1		
354+00 LT	SPEED LIMIT 30	1	24	30	5.00						1		X		X															R2-1		
354+65 RT	Canada	1	72	12	6.00						2									2	152.0									VDI-1		159	
	Beecher Falls VT 2	1	72	12	6.00																									VDI-1A		159	
	Norton VT 13	1	72	12	6.00																									VDI-1A		159	
	New Hampshire	1	72	12	6.00																									VDI-1		159	
355+45 LT	Bloomfield 21	1	72	12	6.00						2		X		X															VD2-1		159	
	SOUTH CONNECTICUT RIVER BYWAY	1	24	12	2.00		1																							GREEN ON WHITE	M3-3		
	VERMONT 102	1	30	24	5.00		1																							MI-5			E-136B
SHEET TOTALS		SF 87.63	SF	EA. 2	SF							FT 120					LB			EA. 4	LB 292.6				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VAOT "SIGN POST DESIGN GUIDELINE."

PROJECT NAME:	LEMINGTON-CANAAN		
PROJECT NUMBER:	STP 2723(I)		
FILE NAME:	z07c214tsdet.dgn	PLOT DATE:	2/28/2015
PROJECT LEADER:	P. SHEDD	DRAWN BY:	W. GORDON
DESIGNED BY:	N. LEMAY	CHECKED BY:	P. SHEDD
TRAFFIC SIGN SUMMARY SHEET II		SHEET	154 OF 162

CLD 14-0197