STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #13

SHSM = FHWA 2004 STANDARD HIGHWAY SIGNS AND MARKINGS BOOK AND THE 2012 SUPPLEMENT TO THE 2004 EDITION

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL		
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	SQUARE STEEL (In)			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In)			FOUND-ATION	TUBULAR STEEL Ø (In)				W-SHAPE STEEL				SIGNS REQUIRED		SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.75	2.0	2.5			3.0	4.0	4.0 MOD		3.0	3.5	4.0	5.0	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE				
												lb/ft					lb/ft				lb/ft											
												1.88	2.42	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6								
C26+44 LT	SPEED LIMIT 25	1	24	30	5.00				1																			INSTALL BELOW RETAINED LEGAL LOAD SIGN	R2-1		
C49+50 RT	$500 MAX FINE THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1		X		X													VR-023b			E-144
C51+05 RT	$500 MAX FINE THROWING TRASH ON HIGHWAYS AND STREAMS	1	24	30	5.00						1		X		X													VR-023b			E-144
C79+50 LT	STATE LAW	1	36	12	3.00						2		X		X													VW-362P		158	
	DRIVERS HAND-HELD ELECTRONIC DEVICES PROHIBITED	1	36	48	12.00																							VR-430		158	
	SUBTOTAL SHEET 144 SUBTOTAL SHEET 145 SUBTOTAL SHEET 146 SUBTOTAL SHEET 147				65.73 63.66 69.62 77.94		15 2 2				470 20		120 90 30 180								4	372.4										
	SUBTOTAL SHEET 148 SUBTOTAL SHEET 149 SUBTOTAL SHEET 150 SUBTOTAL SHEET 151				71.76 75.75 49.75 52.00								195 210 150 240																			
	SUBTOTAL SHEET 152 SUBTOTAL SHEET 153 SUBTOTAL SHEET 154 SUBTOTAL SHEET 155				56.09 60.59 87.63 67.84		1 2				10 10		180 195 120 210								4	292.6										
	SUBTOTAL SHEET 156				30.00								60																			
	ROUNDING				1.64																											
												FT 510	FT 1980	FT		EA	LB	LB	LB			LB 665	LB	LB							
	PROJECT TOTALS				SF 830	SF	EA. 22	SF				FT 2490					LB			EA. 8	LB 665				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VAOT "SIGN POST DESIGN GUIDELINE."

CLD 14-0197

PROJECT NAME: LEMINGTON-CANAAN
PROJECT NUMBER: STP 2723(I)

FILE NAME: z07c214tsdet.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
TRAFFIC SIGN SUMMARY SHEET 13

PLOT DATE: 2/28/2015
DRAWN BY: W. GORDON
CHECKED BY: P. SHEDD
SHEET 156 OF 162