COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2724(I)S				STP 2725(I)S				SUMMARY OF ESTIMATED QUANTITIES				
EMPLOY. TRAINEE.	BRIDGE	FULL C.E.	ROADWAY	EMPLOY. TRAINEE.	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			650				850	1500	CY	EARTH BORROW	203.30	EST.
			1				1	2	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
			1225				1425	2650	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	
			15,500				15,600	31,100	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	
			136,500				131,350	267,850	SY	RECLAIMED STABLIZED BASE	310.20	
			230				185	415	TON	AGGREGATE SHOULDERS	402.12	
			3450				3650	7100	TON	AGGREGATE SHOULDERS, RAP	402.13	
			300				300	600	CWT	EMULSIFIED ASPHALT	404.65	
			1				1	2	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
			11,500				11,000	22,500	CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	
										BEGIN OPTION AA		
			27,250				26,250	53,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% RAP CONTENT)	490.30	
			27,250				26,250	53,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0% < RAP CONTENT < 15.0%)	490.30	
			27,250				26,250	53,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30	
			27,250				26,250	53,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30	
										END OPTION AA		
			1				1	2	LU	AIR VOIDS PAY ADJUSTMEMT (N.A.B.I.)	490.31	
			1				1	2	LU	MAT DENSITY PAY ADJUSTMEMT (N.A.B.I.)	490.32	
			1				1	2	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	
			1				1	2	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	
125					60			185	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	
138					38			176	LF	REMOVAL OF EXISTING RAIL	525.10	
138					38			176	LF	BRIDGE RAILING REPAIR, TYPE III	525.60	
50					50			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
			1					1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
			200				225	425	HR	POWER GRADER RENTAL	608.15	EST.
			175				100	275	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			75				150	225	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
			50				50	100	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			275				150	425	HR	TRUCK RENTAL	608.37	EST.
			200				225	425	HR	LOADER RENTAL, TYPE I	608.40	EST.
			100				100	200	MGAL	DUST CONTROL WITH WATER	609.10	EST.
			10				10	20	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST.
			425				25	450	CY	STONE FILL, TYPE I	613.10	
			135				50	185	EA	YIELDING MARKER POSTS	619.17	EST.

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

COMPOSITE QUANTITY SHEET #1

PROJECT NAME: BRIGHTON - WARREN GORE & WARREN GORE - NORTON

PROJECT NUMBER: STP 2724(I)S & STP 2725(I)S

FILE NAME: p07c216.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07c216quant.i

PLOT DATE: 31-OCT-2011 11:49
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 3 OF 107