QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			7325	7325	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	28.5
			690	690	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POST	621.205	2.5
			280	280	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.4
			50	50	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	
			45	45	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
			4	4	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
			7	7	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
			4	4	EA	GUARDRAIL APPROACH SECTION, GALVANIZED TYPE I	621.70	
			7675	7675	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	6.9
			1	1	EA	ADJUST ELEVATION OF VALVE BOX	629.20	
			2050	2050	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			3050	3050	HR	FLAGGERS	630.15	EST.
		0.5		0.5	LS	FIELD OFFICE, ENGINEERS	631.10	
		0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	
		0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
		0.5		0.5	LU	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.25	
			0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	
			1	1	LS	TRAFFIC CONTROL (STP 2724(I)S)	641.10	
			2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
			82,450	82,450	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	54
			75,850	75,850	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	46.5
			110	110	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	10
			60	60	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	5
			32	32	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
			164,900	164,900	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
			151,700	151,700	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
			120	120	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
			64	64	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	
			12,350	12,350	EA	LINE STRIPING TARGETS	646.76	EST.
			2250	2250	SY	GEOTEXTILE UNDER STONE FILL	649.31	19
			110	110	LB	SEED	651.15	2
			400	400	LB	FERTILIZER	651.18	
			1	1	TON	AGRICULTURAL LIMESTONE	651.20	
			50	50	CY	TOPSOIL	651.35	EST.
			5380	5380	SY	TEMPORARY EROSION MATTING	653.20	23

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #2

PROJECT NAME: BRIGHTON - WARREN GORE

PROJECT NUMBER: STP 2724(I)S

FILE NAME: p07c216.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07c216quan2.i

PLOT DATE: 31-OCT-2011 11:49
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.