STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
BRIGHTON: 302+17.0, LT	BRIDGE 27 VT 114	1	6	8	0.33						1				X			X															SIGN ID CODE VD-701		E-134
302+73.0, LT	RT 114 NORTH RD / FIVE MILE SQUARE RD						1 1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1140 0504 0574	1	6	10	0.42		1																										BACK-TO-BACK SIGN ID CODE VD-700		- E-138
303+15.0, RT	IRON BRIDGE LOOP / IRON BRIDGE LOOP						1 1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1140 0504 0574	1	6	10	0.42		1																										BACK-TO-BACK SIGN ID CODE VD-700		- E-138
307+27.0, LT	SPEED LIMIT 40	1	36	36	9.00						2					X		X															SIGN ID CODE W3-5	68	
309+21.0, RT	IRON BRIDGE LOOP / IRON BRIDGE LOOP						1 1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1140 0504 0586	1	6	10	0.42		1																										BACK-TO-BACK SIGN ID CODE VD-700		E-138
373+52.0, LT	SPEED LIMIT 50	1	24	30	5.00						1					X		X															SIGN ID CODE R2-1		E-142
373+55.0, RT	JCT	1	21	15	2.19						1					X		X															SIGN ID CODE M2-1		E-136B
	VERMONT 111	1	30	24	5.00																												SIGN ID CODE MI-5		E-136B
												LF	LF	LF	LF 14	LF 98	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 22.78	SF	EA. 9	SF							LF			LF 112					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: BRIGHTON - WARREN GORE

PROJECT NUMBER: STP 2724(I)S

FILE NAME: p07c216.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07c216tss2.i

PLOT DATE: 31-OCT-2011 11:52
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 59 OF 107