QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			2800	2800	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	21
			2025	2025	LF	STEEL BEAM GUARDRAIL, GALVANIZED W/ 8 FEET POST	621.205	25
			150	150	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	2.4
			50	50	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216	
			36	36	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
			2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
			6175	6175	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	18
			2050	2050	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
			3100	3100	HR	FLAGGERS	630.15	EST.
		0.5		0.5	LS	FIELD OFFICE, ENGINEERS	631.10	
		0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	
		0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
		0.5		0.5	LU	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.25	
520				520	HR	EMPLOYEE TRAINEESHIP	634.10	
			0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	
			1	1	LS	TRAFFIC CONTROL (STP 2725(I)S)	641.10	
			2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
			87,000	87,000	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	16
			82,500	82,500	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	79
			525	525	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	26
			350	350	LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	21
			85	85	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	8
			33	33	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
			174,000	174,000	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
			165,000	165,000	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
			950	950	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	EST.
			170	170	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
			66	66	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
			13,150	13,150	EA	LINE STRIPING TARGETS	646.76	EST.
			75	75	LF	PAINTED CURB	646.81	6
			50	50	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.
			60	60	LB	SEED	651.15	EST.
			400	400	LB	FERTILIZER	651.18	EST.
			1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
			50	50	CY	TOPSOIL	651.35	EST.
			2000	2000	SY	TEMPORARY EROSION MATTING	653.20	57

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #2

PROJECT NAME: WARREN GORE - NORTON

PROJECT NUMBER: STP 2725(I)S

FILE NAME: p07c218.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p07c218quan2.i

PLOT DATE: 31-OCT-2011 11:53
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 78 OF 107