QUANTITIES

QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		ALT A	ALT B	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					10000		10000	LF	SHOULDER BERM REMOVAL	203.40	EST.
					990		990	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	13
					235		235	TON	AGGREGATE SHOULDERS	402.12	-
					770		770	CWT	EMULSIFIED ASPHALT	404.65	-
					1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
				140			140	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	2
					300		300	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
					350		350	HR	FLAGGERS	630.15	EST.
						1	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	EST.
					1		1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST.
					1		1	LS	TRAFFIC CONTROL	641.10	EST.
					72420		72420	LF	4 INCH WHITE LINE	646.20	-
					72420		72420	LF	4 INCH YELLOW LINE	646.21	-
					5		5	EA	LETTER OR SYMBOL	646.30	EST.
					30		30	LF	CROSSWALK MARKING	646.31	EST.
					900		900	EA	LINE STRIPING TARGETS	646.76	EST.
					25000		25000	LB	SPECIAL PROVISION (BITUMINOUS CRACK SEALING, BLOW AND GO METHOD)	900.635	EST.
					15		15	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
									BEGIN PROJECT BCP ALTERNATE ITEMS		
		7150					7150	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-34)	490.30	-
			7150				7150	TON	SPECIAL PROVISION (6.3 MM POLYMER - MODIFIED BITUMINOUS CONCRETE PAVEMENT) (PG 58-34, SBR LATEX)	900.680	-
									END PROJECT BCP ALTERNATE ITEMS		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING-BIT. PAVEMENT
167	SY	BEGIN PROJECT
334	SY	BRIDGE 48 AND APPROACHES
376	SY	BRIDGE 52 AND APPROACHES/END PROJECT
100	SY	DRIVES AND TOWN HIGHWAYS
13	SY	ROUNDING
990	SY	TOTAL
		PROJECT BITUMINOUS CONCRETE PAVEMENT
6650	TON	MAINLINE
500	TON	LEVELING
7150	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CANAAN
PROJECT NUMBER: STP SURF(7)

FILE NAME: p07c292.dgn
PROJECT LEADER: DOMEY
DESIGNED BY: LOCKE
p07c292qs.i

PLOT DATE: 18-MAY-2009
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 3 OF 7