QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	GOV'T NON-PARTIC.	FULL CE	TRAINING	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
					140	140	CY	COMMON EXCAVATION	203.15	6.8
					85	85	CY	SOLID ROCK EXCAVATION	203.16	0.4
					25	25	CY	EARTH BORROW	203.30	EST
					1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
					46000	46000	SY	COLD PLANING BITUMINOUS PAVEMENT	210.10	352.5
					140	140	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	3.2
					200	200	CWT	EMULSIFIED ASPHALT	404.65	9.4
					1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	-
					5150	5150	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	64.2
					1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	9				19	28	EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-
					46	46	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.
					6	6	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.
					5	5	EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.
					38	38	EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
					50	50	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
					30	30	HR	POWER BROOM RENTAL TYPE II	608.31	EST
					6	6	LF	VERTICAL GRANITE CURB	616.21	-
					590	590	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	9.0
					480	480	LF	REMOVAL OF EXISTING CURB	616.41	5.0
					720	720	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	9.5
					1400	1400	SF	DETECTABLE WARNING SURFACE	618.30	3.0
	25				95	120	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
					2600	2600	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
					5200	5200	HR	FLAGGERS	630.15	EST
		1				1	LS	FIELD OFFICE, ENGINEERS	631.10	-
		1				1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
		3000				3000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-
					1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
					1	1	LS	TRAFFIC CONTROL	641.10	-
					1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
					3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
					9800	9800	LF	DURABLE 4 INCH WHITE LINE, RECESSED POLYUREA	646.406	190.0
					11000	11000	LF	DURABLE 4 INCH YELLOW LINE, RECESSED POLYUREA	646.416	106.0
					4500	4500	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	412.0
					2800	2800	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	202.0

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
45647.5	SY	U.S. ALT. ROUTE 7
352.5	SY	ROUNDING
46000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
		WEARING COURSE
3348.8	TON	TYPE IVS
		SIDEROADS
602.1	TON	TYPE IVS
		LEVELING COURSE
1135.0	TON	TYPE IVS
64.2	TON	ROUNDING
5150	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2722 (I)

FILE NAME: 07d028.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
QUANTITY SHEET #1

PLOT DATE: 05-JUN-2014 11:20
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 8 OF 61