STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET 2

BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAV. CY	203.16 SOLID ROCK EXCAV. CY	203.30 EARTH BORROW CY	204.22 TRENCH EXCAV. OF EARTH, EXP. (N.A.B.I.) CY	301.26 SUBBASE OF CRUSHED GRAVEL CY	604.40 CHANGE ELEV. DI EACH	604.412 REHAB. D.I. CLASS I EACH	604.415 REHAB. D.I. CLASS II EACH	604.418 REHAB. D.I. CLASS III EACH	604.42 CHANGE ELEV. SEWER MANHOLE EACH	616.21 VERTICAL GRANITE CURB LF	616.28 CAST-IN-PLACE CONC CURB, TYPE B LF	616.41 REMOVAL OF EXISTING CURB LF	618.10 P.C.C. SIDEWALK, 5 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	REMARKS
36+24	36+36	LT	1.99	1.66			1.99									11.96	26	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
36+27	36+32	RT	0.41	0.34			0.41									2.48	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
36+32	36+37	RT	0.48	0.40			0.48									2.89	8	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
36+66	36+82	LT	3.22	2.69			3.22									19.34	28	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
36+68	36+81	RT	0.85	0.71			0.85									5.12	24	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
41+95	42+11	LT	1.10	0.91			1.10									6.57	32	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
41+95	42+12	RT	1.86	1.55			1.86									11.18	30	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
42+41	42+53	RT	0.65	0.54			0.65									3.87	20	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
42+41	42+54	LT	0.88	0.74			1.07									6.41	30	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
45+77	45+85	RT	1.07	0.89			1.07									6.41	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
45+81	45+93	LT	1.70	1.42			1.70									10.21	24	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
46+15	46+25	RT	0.99	0.82			0.99									5.92	16	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
46+21	46+32	LT	2.30	1.92			2.30									13.80	31	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
49+91	50+05	LT	1.01	0.84			1.01									6.06	30	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
49+92	50+05	LT												19	19			
49+97	50+06	RT	0.80	0.66			0.80									4.77	14	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 5, EXAMPLE 2 FROM
																		STANDARD DRAWING C-3A
50+60	50+80	RT	3.29	2.74			3.29									19.71	22	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
50+71	50+80	LT	0.79	0.66			0.79									4.76	12	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 5, EXAMPLE 2 FROM
																		STANDARD DRAWING C-3A
54+23	54+36	LT	1.20	1.00			1.20							19	19	7.21	20	REPLACE CONCRETE REQUIRED FOR INSTALLATION OF TRUNCATED DOMES
54+26	54+39	RT	1.83	1.52			1.83									10.97	24	REMOVE AND RECONSTRUCT SIDEWALK RAMP TYPE 6, EXAMPLE 3 FROM
																		STANDARD DRAWING C-3B
SUBTOTAL			26.42	22.01	-	-	26.61	-	-	-	-	-	-	38	38	159.64	415	

ITEM DETAIL SUMMARY SHEET 2

PROJECT NAME: BURLINGTON (CLASS I)
PROJECT NUMBER: STP 2722 (I)

FILE NAME: 07d028.dgn
PROJECT LEADER: CDL
DESIGNED BY: SJL
PLOT FILE: 07d028_12.i

PLOT DATE: 05-JUN-2014 11:20
DRAWN BY: SJL
CHECKED BY: EPD
SHEET 12 OF 61