

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES							TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
	ROADWAY	NO FEDERAL /STATE	BRIDGE	FULL C.E.	GRAND TOTAL	UNIT		ITEMS	ITEM NO.	ROUND	QUANTITIES	UNIT	ITEMS			
	1				1	EACH		THINNING AND TRIMMING FOR SIGNS	201.31	-			COLD PLANING BITUMINOUS PAVEMENT			
	205	530			735	CY		COMMON EXCAVATION	203.15	11.1	76387	SY	MAINLINE - U.S. ROUTE 5			
	375				375	CY		EARTH BORROW	203.30	-	1081	SY	BRIDGE			
	1				1	CY		TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	6817	SY	SIDEROADS			
	86700				86700	SY		COLD PLANING, BITUMINOUS PAVEMENT	210.10	819	1596	SY	DRIVES WITH APRONS GREATER THAN 40'			
	120	280			400	CY		SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	9.3	819	SY	ROUNDING			
	420				420	TON		AGGREGATE SHOULDERS, RAP	402.13	7			SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (TYPE IVS)			
	1				1	LU		PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	6658	TON	MAINLINE - U.S. ROUTE 5 WEARING COURSE			
	10100				10100	TON		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	162	79	TON	BRIDGE			
	1				1	LU		AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-	597	TON	SIDEROADS			
			205		205	LF		BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3	186	TON	DRIVES WITH APRONS GREATER THAN 40'			
			100		100	CF		RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.	2418	TON	LEVELING			
	5				5	EACH		CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.	162	TON	ROUNDING			
	67				67	EACH		REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			STONE FILL, TYPE I			
	17				17	EACH		REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-	133	CY	DITCH CLEANING			
	58				58	EACH		CHANGING ELEVATION OF SEWER MANHOLES	604.42	-	1.9	CY	SLOPE EROSION REPAIR			
	10				10	HR		POWER GRADER RENTAL	608.15	EST.	5.1	CY	ROUNDING			
	100				100	HR		ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			TOTAL			
	30				30	HR		POWER BROOM RENTAL, TYPE I	608.30	EST.						
	55				55	HR		POWER BROOM RENTAL, TYPE II	608.31	EST.						
	200				200	HR		TRUCK RENTAL	608.37	EST.						
	10				10	HR		LOADER RENTAL, TYPE I	608.40	EST.						
	140				140	CY		STONE FILL, TYPE I	613.10	5.1						
	50				50	CY		STONE FILL, TYPE II	613.11	EST.						
	20				20	LF		GRANITE SLOPE EDGING	616.20	-						
	270	3030			3300	LF		VERTICAL GRANITE CURB	616.21	31.1						
	225				225	LF		CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	2.2						
	175				175	LF		TREATED TIMBER CURB	616.35	5						
	22				22	LF		REMOVING AND RESETTING CURB	616.40	0.5						
	690	2980			3670	LF		REMOVAL OF EXISTING CURB	616.41	37.2						
	80				80	TON		BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1						
	1				1	EACH		RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-						
	505	1335			1840	SY		PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	20						
	20	310			330	SY		PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	618.11	6						
	790				790	SF		DETECTABLE WARNING SURFACE	618.30	10						
	18				18	EACH		YIELDING MARKER POSTS	619.17	EST.						
	2050				2050	LF		STEEL BEAM GUARDRAIL, GALVANIZED	621.20	37.5						

PROJECT NAME: NEWPORT
PROJECT NUMBER: STP 2704(I)

FILE NAME: p07d196.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07d196qs01.i

PLOT DATE: 03-APR-2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 4 OF 91