ITEM DETAIL SUMMARY SHEET 2

LOCATION			MISCELLANEOUS													REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	616.41 REMOVAL OF EXISTING CURB LF	616.47 BIT. CONC. GUTTERS & ISLANDS TON	617.10 RELOC. MAILBOX, SINGLE SUPP. EACH	618.10 PORTLAND CEMENT CONC. S.W., 5 INCH SY	618.11 PORTLAND CEMENT CONC. S.W., 8 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	619.17 YIELDING MARKER POSTS EACH	649.31 GEOTEXTILE UNDER STONE FILL SY	651.15 SEED LB	651.40 GRUBBING MATERIAL SY	653.20 TEMPORARY EROSION MATTING SY	676.10 DELINEATOR WITH STEEL POST EACH	676.12 REMOVAL OF EXIST. DELINEATOR EACH	
US ROUTE 5																
CITY OF NEWPORT																
0+00.00	205+33.92	LT&RT		77.2					18		89					QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE SHEET 14.
0+00.00	205+33.92	LT&RT								597	25		1482			SEE DITCH CLEANING DETAIL SHEET
19+79	22+16.5	RT											50	2	1	INSTALL ANCHOR @ STA. 19+79. INSTALL ANCHOR STA. 22+16.5
24+66	28+53.5	RT											50	2		INSTALL ANCHOR @ STA. 24+66. INSTALL TREATED TIMBER CURB FROM STA. 25+03.5 TO 26+73.5. INSTALL ANCHOR @ 28+53.5.
32+15	33+77.5	RT											50	2	1	INSTALL ANCHOR @ STA. 32+15. INSTALL ANCHOR @ STA. 33+77.5
40+51		LT				6.0		8.0								CONSTRUCT SIDEWALK RAMP, TYPE 1
43+61		LT					8.0	8.0								CONSTRUCT SIDEWALK RAMP, TYPE 6
43+73		RT				2.0		8.0								CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
45+65		LT				6.0		8.0								CONSTRUCT SIDEWALK RAMP, TYPE 1
45+95		LT	24.0			13.0		12.0								CONSTRUCT SIDEWALK RAMP, TYPE 6
47+67	63+13	LT	1197.0			662.0	193.0									CONSTRUCT SIDEWALK (5" DEPTH) WITH 8" DEPTH AT ALL DRIVES. REMOVE EXISTING CURB AND INSTALL NEW CURB IN EXISTING LOCATIONS.
50+09	56+07	RT	543.0													INSTALL VERTICAL GRANITE CURB
63+14		RT				3.0		6.0								CONSTRUCT SIDEWALK RAMP, TYPE 1
63+14		LT					3.0	12.0								CONSTRUCT SIDEWALK RAMP, TYPE 6
63+39	66+88	RT	239.0			178.0	20.0	30.0								CONSTRUCT SIDEWALK (5" DEPTH) WITH 8" DEPTH AT ALL DRIVES WITH RAMPS AS SPECIFIED ON LAYOUT SHEETS. REMOVE EXISTING CURB AND INSTALL NEW CURB IN EXISTING LOCATIONS.
63+63	67+70	LT	351.0			190.0	37.0									CONSTRUCT SIDEWALK (5" DEPTH) WITH 8" DEPTH AT ALL DRIVES. REMOVE EXISTING CURB AND INSTALL NEW CURB IN EXISTING LOCATIONS.
68+41		RT				9.0		20.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
68+44		LT	22.0			4.0		14.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
68+51		LT				2.0		8.0								REMOVE BRICKS AND CONSTRUCT SIDEWALK RAMP, TYPE 3
68+71		LT				6.0		8.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
68+71		LT				2.0		8.0								REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
68+95		LT				5.0		14.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
71+23		LT				5.0		8.0								CONSTRUCT SIDEWALK RAMP, TYPE 6
71+40		RT	12.0			2.0		8.0								REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
71+44		LT	16.0			14.0		20.0								CONSTRUCT SIDEWALK RAMP, TYPE 1
73+38		LT				2.0		8.0								REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
73+38		RT				2.0		8.0								REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
73+53		RT				2.0		8.0								CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
73+58		LT				3.0		14.0								REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
73+91		LT				3.0		14.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
73+91		RT				3.0		10.0								CONSTRUCT SIDEWALK RAMP, TYPE 3
SHEET SUBTOTALS:			2404.0	77.2		1124.0	261.0	262.0	18	597	114		1632	6	2	

ITEM DETAIL SUMMARY SHEET #2

PROJECT NAME: NEWPORT CITY
PROJECT NUMBER: STP 2704(1)

FILE NAME: p07d196.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07d196ldss02.i

PLOT DATE: 3/6/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 8 OF 91