ITEM DETAIL SUMMARY SHEET 4

LOCATION			MISCELLANEOUS														REMARKS
			616.41	616.47	617.10	618.10	618.11	618.30	619.17	649.31	651.15	651.40	653.20	676.10	676.12		
BEGIN MILE STA.	END MILE STA.	POS.	REMOVAL OF EXISTING CURB	BIT. CONC. GUTTERS & ISLANDS	RELOC. MAILBOX, SINGLE SUPP.	PORTLAND CEMENT CONC. S.W., 5 INCH	PORTLAND CEMENT CONC. S.W., 8 INCH	DETECTABLE WARNING SURFACE	YIELDING MARKER POSTS	GEOTEXTILE UNDER STONE FILL	SEED	GRUBBING MATERIAL	TEMPORARY EROSION MATTING	DELINEATOR WITH STEEL POST	REMOVAL OF EXIST. DELINEATOR		
			LF	TON	EACH	SY	SY	SF	EACH	SY	LB	SY	SY	EACH	EACH		
74+01		LT				2.0		8.0									REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
74+01		RT				2.0		8.0									REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
76+20	76+35	LT	12.0														REMOVE EXISTING CURB RADII AND REPLACE WITH NEW CURB ALONG MAIN ST. REMOVE EXISTING PAVEMENT BETWEEN SIDEWALK AND CURB THEN TOPSOIL, SEED AND MULCH.
76+91		LT	24.0			28.0		10.0									CONSTRUCT SIDEWALK RAMP, TYPE 5
76+91		RT	19.8			18.0		22.0									CONSTRUCT SIDEWALK RAMP, TYPE 3
77+09		RT				5.0		14.0									CONSTRUCT SIDEWALK RAMP, TYPE 3
77+74		LT				12.0		10.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
77+97		LT	16.8			16.0		12.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
79+63		LT				2.0		8.0									REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
79+63		RT				2.0		10.0									REMOVE BRICKS AND SET DETECTABLE WARNING SURFACE IN BED OF PORTLAND CEMENT CONCRETE
79+67		RT	9.2			5.0		10.0									CONSTRUCT SIDEWALK RAMP, TYPE 3
80+26		RT				10.0		20.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
82+50		RT				2.0		12.0									CONSTRUCT SIDEWALK RAMP, TYPE 5
82+55		LT				2.0		10.0									CONSTRUCT SIDEWALK RAMP, TYPE 5
82+60		RT				2.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
82+92		LT	14.1			10.0		12.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
83+01		RT				2.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
83+28		LT				17.0		12.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
86+36		LT				5.0		16.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
90+26.5	95+64	RT											25	1			CONNECT GUARDRAIL TO EXISTING BRIDGE RAIL @ STA. 90+26.5 INSTALL ANCHOR @ STA. 95+64.
96+88		LT	24.0			8.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1. CONSTRUCT WALK TO BITUMINOUS PATH
96+88		RT	5.0			2.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
105+00		RT				9.0											CONSTRUCT SIDEWALK RAMP APPROACH, TYPE 6
108+35		LT				11.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
108+73		LT				5.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
114+28		RT				2.0		8.0									CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
114+33		LT	11.8			7.0		12.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
114+59		LT	16.8			7.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
115+93		LT	15.2			8.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
116+18		LT	5.8			6.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
118+81		LT	22.5			8.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
119+11		LT	20.2			16.0		22.0									CONSTRUCT SIDEWALK RAMP, TYPE 6
119+17		RT				2.0		8.0									CONSTRUCT SIDEWALK LANDING AND DETECTABLE WARNING SURFACE
122+48		LT	10.4			12.0		8.0									CONSTRUCT SIDEWALK RAMP, TYPE 1
SHEET SUBTOTALS:			227.6			245.0		332.0					25	1			

ITEM DETAIL SUMMARY SHEET #4

PROJECT NAME: NEWPORT CITY
PROJECT NUMBER: STP 2704(1)

FILE NAME: p07d196.dgn
PROJECT LEADER: JLL
DESIGNED BY: STANTEC
IPARM FILE: p07d196ldss04.i

PLOT DATE: 3/6/2012
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 10 OF 91