

ITEM DETAIL SUMMARY SHEET 5

LOCATION			GUARDRAIL				MISCELLANEOUS														REMARKS
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.205	621.60	621.80	203.15	203.30	301.26	402.13	604.40	604.412	604.415	613.10	613.11	616.20	616.21	616.28	616.35	616.40	
			S.B. G.R. GALV. LF	S.B. G.R. GALV. 8' POST LF	ANCHOR FOR S.B. RAIL EACH	REMOVAL & DISPOSAL OF GUARDRAIL LF	COMMON EXCAVATION CY	EARTH BORROW CY	SUBBASE OF CRUSHED GRAV. FINE GRADED CY	AGGREGATE SHOULDERS, RAP TON	CHAN ELEV OF DI, CB OR MH EACH	REHAB DI, CB, OR MH, CLASS I EACH	REHAB DI, CB, OR MH, CLASS II EACH	STONE FILL, TYPE I CY	STONE FILL, TYPE II CY	GRANITE SLOPE EDGING LF	VERTICAL GRANITE CURB LF	C-I-P CONC. CURB, TYPE B LF	TREATED TIMBER CURB LF	REMOVING & RESETTING CURB LF	
122+77		LT					2.4		1.3									14.3			CONSTRUCT SIDEWALK RAMP, TYPE I
124+79		RT					7.8		4.2									20.0			CONSTRUCT SIDEWALK RAMP, TYPE 6. RECONSTRUCT WALKWAY AS SHOWN ON PLANS.
124+84		LT					3.5		1.9									18.2			CONSTRUCT SIDEWALK RAMP, TYPE 6
125+21		LT					2.7		1.5									11.0			CONSTRUCT SIDEWALK RAMP, TYPE I
126+02		RT					2.4		1.3									9.4			CONSTRUCT SIDEWALK RAMP, TYPE I
126+30		RT					1.1		0.6									6.4			CONSTRUCT SIDEWALK RAMP, TYPE I
127+42		LT					1.6		0.9									4.8			CONSTRUCT SIDEWALK RAMP, TYPE I
127+64		LT					2.2		1.2									8.3			CONSTRUCT SIDEWALK RAMP, TYPE I
129+32		RT					1.1		0.6												CONSTRUCT SIDEWALK RAMP, TYPE I
129+55		LT					2.6		1.4									11.4			CONSTRUCT SIDEWALK RAMP, TYPE 6
129+56		RT					3.1		1.7									14.0			CONSTRUCT SIDEWALK RAMP, TYPE 6
133+90		RT					6.4		3.5								40.0				CONSTRUCT SIDEWALK RAMP, TYPE 6
133+95		LT					3.5		1.5												CONSTRUCT SIDEWALK RAMP, TYPE 6
133+95		CL					12.0		9.5							20.0					REMOVE ISLAND FOR CROSSWALK OPENING. CONSTRUCT SIDEWALK AND DETECTABLE WARNING SURFACES. INSTALL GRANITE SLOPE EDGING. SEE DETAIL ON SHEET 16.
134+21		RT					28.8		25.3												REMOVE TRIANGULAR ISLAND, SEE DETAIL ON SHEET 16.
134+34		LT					2.8		1.5								18.0				REMOVE EXISTING SIDEWALK RAMP AND REPLACE WITH LEVEL SIDEWALK
135+02		RT					7.1		3.9								42.0				CONSTRUCT SIDEWALK RAMP, TYPE 6
136+34	142+56	RT					110.2		57.6								619.0				CONSTRUCT SIDEWALK (5" DEPTH) WITH 8" DEPTH AT ALL DRIVES. REMOVE EXISTING CURB AND INSTALL NEW CURB IN EXISTING LOCATIONS.
142+80	145+80	RT	300		2	275		50													INSTALL ANCHOR @ 142+80. INSTALL ANCHOR @ 145+80.
152+07	158+82	RT	675		2	675		50													INSTALL ANCHOR @ 152+07. INSTALL ANCHOR @ 158+82.
163+92	164+02	RT												1.9							REPAIR SLOPE EROSION, SEE DETAIL ON SHEET 15.
173+10	174+10	RT	100		2	96		50													INSTALL ANCHOR @ 173+10. INSTALL ANCHOR @ 174+10.
192+65	194+77.5	RT		212.5	2	212.5		50													INSTALL ANCHOR @ 192+65. REMOVE AND RESET MAILBOX @ STA. 193+01, RT. INSTALL ANCHOR @ 194+77.5.
SHEET 7 SUBTOTALS:			400.0	387.5	6	784.5	443.8	150	230.5	413	5	67	17	133	50		2469.0		170		
SHEET 9 SUBTOTALS:			537.5		1	537.5	78.8	25	40.8								80.9	105.0		21.5	
SHEET 11 SUBTOTALS:			1075.0	212.5	8	1258.5	201.3	200	119.4					1.9		20.0	719.0	117.8			
SUBTOTALS			2012.5	600.0	15	2580.5	723.9	375	390.7	413	5	67	17	134.9	50	20.0	3268.9	222.8	170	21.5	
ROUNDING			37.5	-	-	7	11.1	-	9.3	7	-	-	-	5.1	-	-	31.1	2.2	5	0.5	
TOTALS			2050	600	15	2587.5	735	375	400	420	5	67	17	140	50	20	3300	225	175	22	

**ITEM
DETAIL
SUMMARY
SHEET #5**

PROJECT NAME: NEWPORT CITY	PLOT DATE: 03-APR-2012
PROJECT NUMBER: STP 2704(1)	DRAWN BY: STANTEC
FILE NAME: p07d196.dgn	DESIGNED BY: STANTEC
IPARM FILE: p07d196ids05.i	CHECKED BY: STANTEC
	SHEET 11 OF 91