

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS				
	ROADWAY	EROSION CONTROL	FULL C.E.		GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUND		
	9				9	CY	COMMON EXCAVATION	203.15	1		
	6				6	CY	SOLID ROCK EXCAVATION	203.16	0.6		
	730				730	LF	SHOULDER BERM REMOVAL	203.40	6		
	1				1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.		
	25000				25000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	295		
	8				8	CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	0.7		
	13				13	TON	AGGREGATE SHOULDERS, RAP	402.13	0.8		
	104				104	CWT	EMULSIFIED ASPHALT	404.65	0.4		
	1				1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.		
	3100				3100	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	156		
	1				1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	EST.		
	1				1	EA	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.		
	3				3	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	EST.		
	2				2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	EST.		
	2				2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	EST.		
	20				20	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	EST.		
	70				70	HR	POWER GRADER RENTAL	608.15	EST.		
	70				70	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.		
	25				25	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.		
	40				40	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.		
	40				40	HR	TRUCK RENTAL	608.37	EST.		
	40				40	HR	LOADER RENTAL, TYPE I	608.40	EST.		
	70				70	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	4		
	70				70	LF	REMOVAL OF EXISTING CURB	616.41	4		
	45				45	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1.6		
	50				50	SF	DETECTABLE WARNING SURFACE	618.30	2		
	23				23	EA	YIELDING MARKER POSTS	619.17	-		
	375				375	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	3.5		
	2				2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-		
	315				315	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-		
	4				4	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-		
	960				960	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.		
	2880				2880	HR	FLAGGERS	630.15	EST.		
			0.5		0.5	LS	FIELD OFFICE, ENGINEERS	631.10	-		
			0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	-		
			0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-		
			0.5		0.5	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-		

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
24479	SY	MAINLINE
226	SY	SIDE ROADS
295	SY	ROUNDING
25000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
2188	TON	MAINLINE WEARING COURSE (TYPE IVS)
20	TON	SIDE ROADS WEARING COURSE (TYPE IVS)
736	TON	LEVELING (TYPE IVS)
156	TON	ROUNDING
3100	TON	TOTAL

PROJECT NAME: NEWPORT CITY	PLOT DATE: 29-JAN-2013 09:2
PROJECT NUMBER: STP 2719(I)	DRAWN BY: STANTEC
FILE NAME: 07D202.dgn	CHECKED BY: JLL
PROJECT LEADER: JLL	SHEET 8 OF 62
DESIGNED BY: MCF	
IPARM FILE: 07D202_08.i	